

	TECHNICAL SPECIFICATION		Nº: I-ET-3010.2D-1251-560-P4X-002						
	CLIENT: AGUP		SHEET: 1 of 24						
	JOB: HIGH CAPACITY FPSO - GAS EXPORTATION ALL ELECTRIC								
	AREA: ATAPU 2 AND SÉPIA 2		-						
SRGE	TITLE: VACUUM DEAERATION UNIT (UT-1251003)		INTERNAL						
			ESUP						
MICROSOFT WORD / V.2010 / I-ET-3010.2D-1251-560-P4X-002_0.DOCX									
INDEX OF REVISIONS									
REV.	DESCRIPTION AND/OR REVISED SHEETS								
0	ORIGINAL ISSUE								
	REV. 0	REV. A	REV. B	REV. C	REV. D	REV. E	REV. F	REV. G	REV. H
DATE	SEP/12/22								
DESIGN	EEA								
EXECUTION	HR7W								
CHECK	HXG3								
APPROVAL	U32N								
INFORMATION IN THIS DOCUMENT IS PROPERTY OF PETROBRAS, BEING PROHIBITED OUTSIDE OF THEIR PURPOSE									
FORM OWNED TO PETROBRAS N-0381 REV. L									

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 2 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

SUMMARY

1	OBJECTIVE	3
2	NORMATIVE REFERENCES AND DESIGN SPECIFICATIONS	3
3	DEFINITIONS AND ABBREVIATIONS	8
4	GENERAL REQUIREMENTS.....	9
5	PACKAGE SPECIFICATION.....	10
6	NAMEPLATES	18
7	TAG NUMBERING	19
8	CERTIFICATION REQUIREMENTS.....	19
9	REPAIR	19
10	INSPECTION, TESTING AND COMMISSIONING	19
11	SELLER RESPONSIBILITY	23
12	PREPARATION FOR SHIPMENT	24

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 3 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

1 OBJECTIVE

This Technical Specification covers the minimum requirements for design, engineering, materials, fabrication, inspection, testing, commissioning, and pre-commissioning of the VACUUM DEAERATION UNIT (UT-1251003).

VACUUM DEAERATION UNIT (UT-1251003) shall be provided with all necessary instruments to operate safely, adequately and without interruption in an offshore facility.

The requirements herein listed apply to all players which will perform any activity related to the scope of this unit, including manufacturers, packagers, main contractor, subcontractors, suppliers, sub-suppliers, integrators, constructors, and all technical personnel involved. Within the scope of this document, they are all referred to as being a SELLER.

In addition to the requirements of this technical specification, the SELLER shall follow all the requirements of Exhibit I (SCOPE OF WORK), as well as Exhibit III (DIRECTIVES FOR ENGINEERING EXECUTION), Exhibit IV (DIRECTIVES FOR CONSTRUCTION AND ASSEMBLY), Exhibit V (DIRECTIVES FOR PROCUREMENT), Exhibit VI (DIRECTIVES FOR PLANNING AND CONTROL), Exhibit VII (DIRECTIVES FOR QUALITY MANAGEMENT SYSTEM) and Exhibit VIII (DIRECTIVES FOR COMMISSIONING PROCESS).

2 NORMATIVE REFERENCES AND DESIGN SPECIFICATIONS


2.1 CLASSIFICATION SOCIETY


- 2.1.1 SELLER shall perform the work in accordance with the requirements of the Classification Society.
- 2.1.2 SELLER is responsible to submit to Classification Society the documentation in compliance with stated Rules.
- 2.1.3 Classification Society rules may only be waived upon formal approval from the Classification Society itself and from BUYER.

2.2 CODES AND STANDARDS

- 2.2.1 The following codes and standards include provisions that, through reference in this text, constitute provisions of this specification. The latest issue of the references shall be used unless otherwise agreed.
- 2.2.2 Other recognized international standard may be used, whether they meet or exceed the requirements of the standards referenced below. Formal approval from BUYER and from the Classification Society is also required.

AISC ASD - Steel Construction Manual

	TECHNICAL SPECIFICATION		Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA: ATAPU 2 AND SÉPIA 2		SHEET 4 of 24	
	TITLE: VACUUM DEAERATION UNIT (UT-1251003)		INTERNAL	
			ESUP	
API RP 14C	- Recommended Practice for Analysis, Design, Installation and Testing of Basic Surface Safety Systems for Offshore Production Platforms			
API RP 14E	- Recommended Practice for Design and Installation of Offshore Production Platform Piping Systems			
API RP 14J	- Recommended practice for design and Hazard Analysis for Offshore Production Facilities			
API RP 14FZ	- Recommended Practice for Design and Installation Of Electrical Systems For Fixed And Floating Offshore Petroleum Facilities For Unclassified And Class 1, Zone 0,1 And 2 Locations			
API RP 505	- Classification of locations for Electrical Installations at Petroleum Facilities Classified as Class 1, Zone 0, Zone 1 and Zone 2			
API STD 521	- Pressure-relieving and Depressuring			
API STD 681	- Liquid Ring Compressors and Vacuum Pumps in Petroleum, Chemical, and Gas Industry Services			
ASME B16.5	- Pipe Flanges and Flanged Fittings			
ASME B16.47	- Large Diameter Steel Flanges: NPS 26 through NPS 60			
ASME B31.3	- Process Piping			
ASME BPVC VIII	- Div.1 and Div. 2. Boiler and Pressure Vessel Code. Rules for Construction of Pressure Vessels			
ASME BPVC X	- Fiber-Reinforced Plastic Pressure Vessels			
DOT-3A	- Specification for Seamless Steel Transportable Pressure Receptacles			
DOT-3AA	- Specification for Seamless Steel Transportable Pressure Receptacles			
IEC 60079 (all parts)	- Explosive Atmospheres			
IEC 61892 (all parts)	- Mobile and fixed offshore units – Electrical installations			
ISO 21457	- Materials selection and corrosion control for oil and gas production systems			
ISO 9809 (all parts)	- Gas cylinders — Design, construction and testing of refillable seamless steel gas cylinders and tubes			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 5 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

2.3 GOVERNMENT REGULATION

Brazilian Government regulations are mandatory and shall prevail, if more stringent, over the requirements of this specification and other references herein.

NR-10	Brazilian Regulatory Standard - Safety in Electrical Facilities and Services
NR-12	Brazilian Regulatory Standard – Safety Working with Machineries and Equipment.
NR-13	Brazilian Regulatory Standard - Boilers, Pressure Vessels, Pipes and Metallic Storage Tanks
NR-17	Brazilian Regulatory Standard - Ergonomics
NR-26	Brazilian Regulatory Standard - Safety Signing
NR-37	Brazilian Regulatory Standard - Safety and Health in Petroleum Platforms
IBAMA	Brazilian IBAMA environmental regulations concerning the discharge of all types of effluents
INMETRO	INMETRO Resolution nº 115, March 21 st 2022, and its annexes

2.4 DESIGN SPECIFICATIONS

I-ET-3010.00-1200-940-P4X-002 – GENERAL TECHNICAL TERMS

I-ET-3A26.00-1000-941-PPC-001_F – METOCEAN DATA – UNITS AND PRODUCTION SYSTEMS – SANTOS BASIN CENTRAL CLUSTER REGION

I-ET-3A36.00-1000-941-PPC-001_F – METOCEAN DATA – PRODUCTION SYSTEM AND UNITS – NOTHERN SANTOS BASIN PRE-SALT FIELDS

I-RL-3010.2D-1350-960-P4X-002 – MOTION ANALYSIS

I-DE-3010.2D-1200-942-P4X-002 – GENERAL ARRANGEMENT

I-DE-3010.2D-1422-942-P4X-001 – M-11 – WATER INJECTION AND SULPHATE REMOVAL UNIT – EQUIPMENT LAYOUT PLAN


I-DE-3010.2D-1200-94A-P4X-001 – AREA CLASSIFICATION - GENERAL


I-ET-3000.00-5400-98G-P4X-001 – EXPLOSION STUDY

I-ET-3010.00-1200-300-P4X-001 – NOISE AND VIBRATION CONTROL REQUIREMENTS

I-FD-3010.2D-1251-560-P4X-003 – VACUUM DEAERATION UNIT (UT-1251003)

I-DE-3010.2D-1251-944-P4X-005 – VACUUM DEAERATION UNIT

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 6 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP
<p>I-DE-3010.2D-5111-943-P4X-001 – UTILITY FLOW DIAGRAM SEA WATER SYSTEM</p> <p>I-ET-3010.2D-1200-200-P4X-001 – PIPING SPECIFICATION FOR TOPSIDE</p> <p>I-ET-3010.2D-1200-200-P4X-005 – MINIMUM REQUIREMENTS FOR PIPING MECHANICAL DESIGN AND LAYOUT</p> <p>I-ET-3010.2D-1200-200-P4X-006 – REQUIREMENTS FOR PIPING STRESS ANALYSIS</p> <p>I-ET-3010.2D-1200-200-P4X-004 – REQUIREMENTS FOR PIPING SUPPORT</p> <p>I-ET-3010.00-1200-200-P4X-115 – REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING</p> <p>I-ET-3010.00-1200-431-P4X-001 – THERMAL INSULATION FOR MARITIME INSTALLATIONS</p> <p>I-ET-3010.00-1200-251-P4X-001 – REQUIREMENTS FOR BOLTING MATERIALS</p> <p>I-ET-3010.00-1200-200-P4X-116 – REQUIREMENTS FOR BOLTED JOINTS ASSEMBLY AND MANAGEMENT</p> <p>I-DE-3010.00-1400-140-P4X-004 – GENERAL NOTES FOR TOPSIDES STRUCTURES</p> <p>I-ET-3010.2D-1200-940-P4X-001 - MATERIAL SELECTION PHILOSOPHY FOR DETAILED DESIGN</p> <p>I-ET-3010.00-1200-956-P4X-002 – GENERAL PAINTING</p> <p>I-ET-3010.00-1200-310-P4X-001 - API 610 CENTRIFUGAL PUMPS SPECIFICATION</p> <p>I-ET-3010.00-1200-310-P4X-002 – POSITIVE DISPLACEMENT PUMPS SPECIFICATION</p> <p>I-ET-3010.00-1200-310-P4X-003 – NON-API 610 CENTRIFUGAL PUMPS SPECIFICATION</p> <p>I-ET-3010.00-1200-540-P4X-001 – REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION</p> <p>I-ET-3010.00-1200-451-P4X-001 – REQUIREMENTS FOR SHELL AND TUBE HEAT EXCHANGER DESIGN AND FABRICATION</p> <p>I-ET-3010.00-1200-456-P4X-001 – REQUIREMENTS FOR PLATE HEAT EXCHANGER DESIGN AND FABRICATION</p> <p>I-ET-3010.00-1200-510-P4X-001 – METALLIC TANKS DESIGN FOR TOPSIDE</p>			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	
		SHEET 7 of 24	INTERNAL
		ESUP	

I-ET-3010.00-1200-500-P4X-001 – NON-METALLIC TANKS AND PRESSURE VESSELS DESIGN

I-ET-3010.2D-1350-196-P4X-001 - ERGONOMICS REQUIREMENTS FOR TOPSIDES

DR-ENGP-M-I-1.3 – SAFETY ENGINEERING GUIDELINE

I-MD-3010.2D-1200-947-P4X-003 - DESCRIPTIVE MEMORANDUM – SAFETY

I-FD-3010.2D-5400-947-P4X-001 - SAFETY DATA SHEET - TOPSIDE

I-ET-3010.00-5400-947-P4X-002 – SAFETY SIGNALLING

I-ET-3010.00-1200-800-P4X-002 – AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS

I-ET-3010.2D-1200-800-P4X-014 – AUTOMATION INTERFACE OF PACKAGED UNITS

I-ET-3010.00-5520-888-P4X-001 - AUTOMATION PANELS

I-ET-3010.00-5140-712-P4X-001 – LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS

I-ET-3010.00-5140-712-P4X-002 – MEDIUM-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS

I-ET-3010.00-5140-700-P4X-002 – SPECIFICATION FOR ELECTRICAL MATERIAL FOR OFFSHORE UNITS

I-ET-3010.00-5140-700-P4X-007 – SPECIFICATION FOR GENERIC ELECTRICAL EQUIPMENT FOR OFFSHORE UNITS


I-ET-3010.00-5140-700-P4X-009 – GENERAL REQUIREMENTS FOR ELECTRICAL MATERIAL AND EQUIPMENT FOR OFFSHORE UNITS

I-ET-3010.00-5140-741-P4X-004 – SPECIFICATION FOR LOW-VOLTAGE GENERIC ELECTRICAL PANELS FOR OFFSHORE UNITS

I-ET-3010.00-5140-700-P4X-001 – SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS

I-ET-3010.00-5140-700-P4X-003 – ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS

I-DE-3010.00-5140-700-P4X-003 – GROUNDING INSTALLATION TYPICAL DETAILS.

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	
		SHEET 8 of 24	INTERNAL
		ESUP	

I-ET-3010.00-5140-797-P4X-001 – ELECTRICAL SYSTEM AUTOMATION ARCHITECTURE

I-DE-3010.00-5140-797-P4X-002 – ELECTRICAL SYSTEM AUTOMATION TYPICAL ACTUATION DIAGRAMS

I-LI-3010.00-5140-797-P4X-001 – ELECTRICAL SYSTEM AUTOMATION INTERFACE SIGNALS LIST

I-ET-3010.00-5518-767-PPT-002 - TOPSIDES PUBLIC ADDRESS SYSTEM

I-MD-3010.00-5510-760-PPT-001 - GENERAL CRITERIA FOR TELECOMMUNICATIONS DESIGN

DR-ENGP-I-1.15 – COLOR CODING

I-ET-3000.00-1200-940-P4X-001 – TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN

I-ET-3010.00-1200-970-P4X-003 - REQUIREMENTS FOR PERSONNEL QUALIFICATION AND CERTIFICATION

I-ET-3010.00-1200-972-P4X-006 - REQUIREMENTS FOR MANUFACTURING SURVEY INSPECTION

I-ET-3010.00-1200-978-P4X-005 - REQUIREMENTS FOR MATERIALS TRACEABILITY

I-ET-3010.00-1200-970-P4X-013 - COMPLIANCE WITH NR-13 AND SPIE REQUIREMENTS

I-ET-3010.00-1200-955-P4X-001 – WELDING

I-ET-3010.00-1200-970-P4X-004 - NON-DESTRUCTIVE TESTING REQUIREMENTS FOR METALLIC AND NON-METALLIC MATERIALS


2.5 CONFLICTING REQUIREMENTS

2.5.1 In case of conflicting requirements between this technical specification and other cited references, the most stringent shall prevail. If necessary, the SELLER may revert to BUYER for clarification.

3 DEFINITIONS AND ABBREVIATIONS

3.1 DEFINITIONS

3.1.1 All Terms and definitions are established in the latest revision I-ET-3010.00-1200-940-P4X-002 – GENERAL TECHNICAL TERMS

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 9 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

3.2 ABBREVIATIONS

AEPR	- Automation & Electrical Panel Room
CLASS	- Classification Society
FAT	- Factory Acceptance Test
FPSO	- Floating Production Storage and Offloading
GRP	- Glass- Reinforced Plastic
HAZOP	- Hazard and Operability Study
ITP	- Inspection and Test Plans
NPS	- Nominal Pipe Size
NDT	- Non-Destructive Test
PHA	- Process Hazards Analyses
PAGA	- Public Address and General Alarm
PP	- Polypropylene
SS	- Stainless steel

4 GENERAL REQUIREMENTS

4.1 OPERATION ENVIRONMENT

- 4.1.1 The equipment supplied shall be suitable for the environment and range of ambient condition defined in the following documents: for SÉPIA field see I-ET-3A26.00-1000-941-PPC-001_F – METOCEAN DATA – UNITS AND PRODUCTION SYSTEMS – SANTOS BASIN CENTRAL CLUSTER REGION; for ATAPU field see I-ET-3A36.00-1000-941-PPC-001_F – METOCEAN DATA – PRODUCTION SYSTEM AND UNITS – NOTHERN SANTOS BASIN PRE-SALT FIELDS.


4.2 MOTION REQUIREMENTS


- 4.2.1 The necessary design data and information on motion requirements are given in I-RL-3010.2D-1350-960-P4X-002 – MOTION ANALYSIS.

4.3 PACKAGE LOCATION AND AREA CLASSIFICATION

- 4.3.1 The Vacuum Deaeration Unit (UT-1251003) shall be installed on module M-11 as informed in I-DE-3010.2D-1200-942-P4X-002 – GENERAL ARRANGEMENT. For available space, also see I-DE-3010.2D-1422-942-P4X-001 – M-11 – WATER INJECTION AND SULPHATE REMOVAL UNIT – EQUIPMENT LAYOUT PLAN.
- 4.3.2 For area classification see I-DE-3010.2D-1200-94A-P4X-001 – AREA CLASSIFICATION - GENERAL.

4.4 DESIGN LOADS

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 10 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP
<p>4.4.1 In addition to the loads required by the International Standards and loads due to FPSO motion described in I-RL-3010.2D-1350-960-P4X-002 – MOTION ANALYSIS, the following design loads shall be considered whenever applicable:</p> <ul style="list-style-type: none"> • Equipment transportation and erection loads; • Nozzle loads; • Thermal loads; • Wind loads (see METOCEAN DATA); • Weight loads. • Blast loads (according to I-ET-3000.00-5400-98G-P4X-001 – EXPLOSION STUDY) <p>4.5 DESIGN LIFETIME</p> <p>4.5.1 SELLER shall design and fabricate the complete package and each equipment belonging to the scope of supply considering a minimum lifetime of 30 years.</p> <p>4.6 NOISE AND VIBRATION</p> <p>4.6.1 Noise and vibration control concerning human exposure shall be performed according to I-ET-3010.00-1200-300-P4X-001 – NOISE AND VIBRATION CONTROL REQUIREMENTS.</p> <p>5 PACKAGE SPECIFICATION</p> <p>5.1 SCOPE OF SUPPLY</p> <p>5.1.1 SELLER shall select manufacturers considering a proven experience supplying this type of equipment/technology. SELLER shall submit manufacturers names to BUYER approval.</p> <p>5.1.2 The Vacuum Deaeration Unit (UT-1251003) shall be complete in all respect and the scope of supply shall include but not be limited to the major equipment described in the document I-FD-3010.2D-1251-560-P4X-003 – VACUUM DEAERATION UNIT (UT-1251003) and I-DE-3010.2D-1251-944-P4X-005 – VACUUM DEAERATION UNIT.</p> <p>5.1.3 The scope of supply of the Vacuum Deaeration Unit (UT-1251003) shall also include the following major systems: D-UT-1251003 – Vacuum Deaerator Column and the Z-UT-1251003 – Vacuum System.</p> <p>5.1.4 The major equipment of the Vacuum System (Z-UT-1251003) shall also include:</p> <ul style="list-style-type: none"> • 1x100% atmospheric ejector, • 2X100% vacuum pump (B-Z-UT-1251003 A/B), • 2X100% vacuum pump motors, • 1X100% discharge separator tank, • 1X100% unit control panel (PN-Z-UT-1251003) <p>5.2 PROCESS DESIGN</p>			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 11 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

5.2.1 SELLER shall design and size the package and all equipment related to the scope of supply for the full range of process conditions as specified in the following documents:

- A. Process Data Sheet I-FD-3010.2D-1251-560-P4X-003 – VACUUM DEAERATION UNIT (UT-1251003);
- B. Piping and Instrument Diagram: I-DE-3010.2D-1251-944-P4X-005 – VACUUM DEAERATION UNIT
- C. Flow Diagram: I-DE-3010.2D-5111-943-P4X-001 – UTILITY FLOW DIAGRAM SEA WATER SYSTEM.

5.2.2 Design shall also include the definition of number, size and location of all nozzles related to the process and instruments in the battery limits of the package (refer to the I-DE-3010.2D-1251-944-P4X-005 – VACUUM DEAERATION UNIT).

5.2.3 Vacuum Pumps

- A. Vacuum pumps (B-Z-UT-1251003 A/B) shall be provided with spacer couplings, including non-sparking coupling guards.
- B. The vacuum liquid ring pumps shall be supplied in accordance with API STD 681.
- C. Vacuum liquid ring pumps shall be supplied with: flowmeter for each pump, level transmitter, water sealing temperature measurement, bearing vibration sensor.

5.2.4 Discharge Separator Tank

- A. Discharge separator tank stiffeners shall be internal where necessary.

5.2.5 Unit Control Panel

- A. Unit Control Panel (PN-Z-UT-1251003) supplied loose to be installed on FPSO module.
- B. Unit Control Panel (PN-Z-UT-1251003) shall be installed in the Topside AEPR, which is a non-hazardous area.
- C. The panel shall be capable of carrying out interlocking, process automation and start-up, shutdown, normal operation and safety procedures.

5.3 MECHANICAL AND PIPING


5.3.1 All piping shall have valves (on/off valves) and/or flanges and blind flanges (ASME B16.5 or ASME B16.47) at the end of unit limits.


5.3.2 SELLER shall follow the technical specification I-ET-3010.2D-1200-200-P4X-001 – PIPING SPECIFICATION FOR TOPSIDE. Alternative piping specifications shall be submitted to BUYER for approval.

5.3.3 Piping layout shall observe the requirements presented in I-ET-3010.2D-1200-200-P4X-005 – MINIMUM REQUIREMENTS FOR PIPING MECHANICAL DESIGN AND LAYOUT

5.3.4 Piping stress analysis shall be performed according to I-ET-3010.2D-1200-200-P4X-006 – REQUIREMENTS FOR PIPING STRESS ANALYSIS.

5.3.5 All piping shall be properly supported considering the service loads, shipment and transportation loads. Piping supports shall be in accordance with I-ET-3010.2D-1200-200-P4X-004 – REQUIREMENTS FOR PIPING SUPPORT. The supporting and installation shall enable piping removal without disturbing structural members.

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 12 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP
<p>5.3.6 Socket welds are only permitted for piping sizes up to NPS 1½. All piping above NPS 1½ shall be butt-welded.</p> <p>5.3.7 Valves shall be selected in conformance with I-ET-3010.2D-1200-200-P4X-001 – PIPING SPECIFICATION FOR TOPSIDE. Alternative valves specifications shall be submitted to BUYER for approval.</p> <p>5.3.8 The use of concentric type butterfly valves and straight-through diaphragm valves with open body (open body tubular diaphragm valves) is not permitted.</p> <p>5.3.9 The use of elastomeric throttle valves exposed to ultraviolet (UV) radiation is not allowed.</p> <p>5.3.10 Sampling point / facilities shall be provided complete with necessary fittings and valves, and the design should reflect nature of the fluids being sampled.</p> <p>5.3.11 Utility hose stations shall be installed throughout the package on strategic places for maintenance and cleaning purposes.</p> <p>5.3.12 The design, assembly and commissioning of all process piping shall be according to ASME B31.3 code, I-ET-3010.00-1200-200-P4X-115 – REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING, and I-ET-3010.2D-1200-200-P4X-005 – MINIMUM REQUIREMENTS FOR PIPING MECHANICAL DESIGN AND LAYOUT.</p> <p>5.3.13 All structural supports including main structural skid, support frames, supports for equipment, ladders, walkways, platforms, grating and drip trays shall be provided.</p> <p>5.3.14 All other miscellaneous items and equipment which are required for the service and proper operation of the Sulphate Removal Unit shall be included.</p> <p>5.3.15 Equipment and piping subjected to a temperature of 60°C and above shall receive a personal protection system by means of stainless steel 316 wire mesh / perforated plates. Alternatively, a thermal insulation may be applied. Equipment and piping in which heat conservation is necessary shall be thermal insulated. The thermal insulation shall be according to the latest revision of I-ET-3010.00-1200-431-P4X-001 – THERMAL INSULATION FOR MARITIME INSTALLATIONS.</p> <p>5.3.16 All fasteners (studs, bolts, tightening bolts, and nuts) shall be according to I-ET-3010.00-1200-251-P4X-001 – REQUIREMENTS FOR BOLTING MATERIALS.</p> <p>5.3.17 Bolted joints within the package shall be assembled and managed as established in I-ET-3010.00-1200-200-P4X-116 – REQUIREMENTS FOR BOLTED JOINTS ASSEMBLY AND MANAGEMENT.</p> <p>5.3.18 SELLER shall provide a design book with all piping detailed design documentation, which must include, but not be limited, to the following documents: isometrics, piping plan, support detail drawings, stress analysis report (with native program file), list of supports, valve list, special item list, document list, stress analysis list, tie-in list, welding procedures, strainers datasheet, and piping elements datasheet.</p> <p>5.4 STRUCTURES</p> <p>5.4.1 SELLER shall follow the requirements of I-DE-3010.00-1400-140-P4X-004 – GENERAL NOTES FOR TOPSIDES STRUCTURES.</p>			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 13 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP

5.5 MATERIAL SELECTION AND CERTIFICATION


- 5.5.1 The SELLER is responsible for the materials selection considering the philosophy detailed at I-ET-3010.2D-1200-940-P4X-001 - MATERIAL SELECTION PHILOSOPHY FOR DETAILED DESIGN, suitable to the operational condition shown in the process data sheet I-FD-3010.2D-1251-560-P4X-003 – VACUUM DEAERATION UNIT (UT-1251003).
- 5.5.2 Materials of construction for the Vacuum Deaerator Column (D-UT-1251003) shall be carbon steel with internal coating in accordance with I-ET-3010.00-1200-956-P4X-002 – GENERAL PAINTING.
- 5.5.3 Materials for the internals of the vacuum deaerator column shall be in SS 316L, PP or GRP.
- 5.5.4 The materials of construction for the liquid ring pumps and the ejectors shall be 25% Cr duplex.
- 5.5.5 Separator tank shall be made of GRP.
- 5.5.6 SELLER may offer materials of construction other than those specified, but these shall be quoted separately as an alternative.
- 5.5.7 In all cases, SELLER shall submit the detailed material selection report, including all piping, equipment and their components, for BUYER approval prior to manufacturing activities.
- 5.5.8 SELLER shall be responsible for obtaining all necessary certification of the equipment, work, and materials.
- 5.5.9 SELLER through the independent certifying authority shall supply all certificates related to the materials, inspections, tests, and qualification activities detailed in the approved Quality Plan.

5.6 DESIGN AND FABRICATION

5.6.1 Pump

- A. For Vacuum Pumps (B-Z-UT-1251003 A/B), SELLER shall follow the requirements presented in item 5.2.3 Vacuum Pumps.
- B. If necessary the use of additional pumps for the proper operation of the unit, SELLER shall follow the requirements and selection material in compliance with I-ET-3010.00-1200-310-P4X-001 - API 610 CENTRIFUGAL PUMPS SPECIFICATION, I-ET-3010.00-1200-310-P4X-002 – POSITIVE DISPLACEMENT PUMPS SPECIFICATION, or I-ET-3010.00-1200-310-P4X-003 – NON-API 610 CENTRIFUGAL PUMPS SPECIFICATION.
- C. For pumps up to 7.5 kW, working with non-flammable and non-hazardous service, SELLER may use its own specification, i.e., no specific design code may be applicable. In this case, additional requirements shall be submitted for BUYER's approval which include field-proven acceptance and material selection performed per ISO 21457.

5.6.2 Pressure Vessel

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 14 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

All pressure vessels, columns and filters shall comply with the requirements of NR-13 (Brazilian Regulatory Standard) and I-ET-3010.00-1200-540-P4X-001 – REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION.

Note: If the scope of supply includes any transportable pressure vessel connected with process plant or platform installations, these items shall be within the scope of NR-13 regulation. Furthermore, transportable containers shall be designed, constructed, inspected and installed in accordance with the requirements addressed by a specific rules of transportable equipment, such as ISO 9809, DOT-3A, or DOT-3AA.

5.6.3 Heat Exchanger

Heat exchangers shall comply with the requirements of I-ET-3010.00-1200-451-P4X-001 – REQUIREMENTS FOR SHELL AND TUBE HEAT EXCHANGER DESIGN AND FABRICATION or I-ET-3010.00-1200-456-P4X-001 – REQUIREMENTS FOR PLATE HEAT EXCHANGER DESIGN AND FABRICATION.

5.6.4 Metallic Tank

Metallic tanks shall comply with the requirements of I-ET-3010.00-1200-510-P4X-001 – METALLIC TANKS DESIGN FOR TOPSIDE.

5.6.5 Non-Metallic Tank and Non-Metallic Pressure Vessel

Non-metallic tanks and non-metallic pressure vessels shall comply with the requirements of I-ET-3010.00-1200-500-P4X-001 – NON-METALLIC TANKS AND PRESSURE VESSELS DESIGN.

5.7 ERGONOMIC REQUIREMENTS


5.7.1 The package shall be arranged such to allow safe and good personnel access for all operation and maintenance activities and in accordance with I-ET-3010.2D-1350-196-P4X-001 - ERGONOMICS REQUIREMENTS FOR TOPSIDES.

5.7.2 SELLER shall prepare detailed assembly, disassembly, and maintenance procedures, describing the use of all involved handling devices and including all required preventive and corrective maintenance tasks. SELLER shall inform the need for disassembling any component or equipment to facilitate access for maintenance. Suitable maintenance routes shall be provided to remove the main components and auxiliaries, avoiding interference with structures, piping, cabling, electric conduits and supports, equipment etc. This plan shall be submitted to BUYER for approval.

5.7.3 All valves shall be positioned with the stem pointing upwards. They shall be located in such a way that the hand wheel or actuator will not obstruct walkways and be easily accessible for operation and maintenance, according to I-ET-3010.2D-1350-196-P4X-001 - ERGONOMICS REQUIREMENTS FOR TOPSIDES. Where hand operated valves are not easily operable, gear operated valves shall be used.

5.7.4 Ladders and platform shall be provided to access operational devices, e.g., valves, instruments, manways, etc., whether located in an elevation greater than 1.75 m over the module base plate.

5.7.5 The level gauges shall be installed in such position that the level indicated in receiver will be easily seen. All level gauges shall have flanged connections, which can be

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 15 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP

isolated, and be complete with vent and drain, valves and connection, to facilitate the maintenance tasks.

5.8 SAFETY REQUIREMENTS


- 5.8.1 Pressure relief system and devices shall comply with the requirements of API STD 521.
- 5.8.2 For area classification see I-DE-3010.2D-1200-94A-P4X-001 – AREA CLASSIFICATION - GENERAL.
- 5.8.3 Mandatory safety items, as established in DR-ENGP-M-I-1.3 – SAFETY ENGINEERING GUIDELINE are to be considered complementary requirements, to the pertinent extent. In case of items in conflict with this document, BUYER shall be consulted.
- 5.8.4 Safety design additional requirements see: I-MD-3010.2D-1200-947-P4X-003 - DESCRIPTIVE MEMORANDUM – SAFETY, and I-FD-3010.2D-5400-947-P4X-001 - SAFETY DATA SHEET - TOPSIDE.
- 5.8.5 HAZOP and PHA shall be performed according to DR-ENGP-M-I-1.3 – SAFETY ENGINEERING GUIDELINE.
- 5.8.6 Double block & bleed arrangements are required for isolation of equipment in piping classes of 300# and above.
- 5.8.7 All safety signs and notices shall be in Portuguese language and according to I-ET-3010.00-5400-947-P4X-002 – SAFETY SIGNALLING.


5.9 INSTRUMENTATION


- 5.9.1 All instrumentation equipment and interface with FPSO automation and control design shall comply with I-ET-3010.00-1200-800-P4X-002 – AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS.
- 5.9.2 For package automation type classification and additional interfaces see I-ET-3010.2D-1200-800-P4X-014 – AUTOMATION INTERFACE OF PACKAGED UNITS.
- 5.9.3 All control, monitoring and safety protection instruments, instrumented valves, devices and associated accessories (such as, but not limited to, tubings thermowells, etc.) for remote indication, control, alarms, protection and shut down, etc. shall be included.
- 5.9.4 Automatic temperature control facilities shall be provided for the control of cooling medium flow.
- 5.9.5 Package Unit Control Panel and Remote I/O Panel shall fully comply with requirements of I-ET-3010.00-5520-888-P4X-001 - AUTOMATION PANELS.

5.10 ELECTRICAL

- 5.10.1 All materials and equipment proper to be used in hazardous areas shall have conformity certificates complying with: the latest revision of IEC 60079 and all its parts; PORTARIA INMETRO Nº 115 (march 21st, 2022); and shall be approved by CLASS.

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 16 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP
<p>5.10.2 Electrical equipment installed in external safe areas, that shall be kept operating during emergency shutdown ESD-3P and ESD-3T shall be certified for installation in hazardous areas Zone 2 (EPL Gc) Group IIA temperature T3, unless they are automatically disconnected if there is gas in the equipment area, according to IEC 61892-1.</p> <p>5.10.3 Low-voltage and medium-voltage motors inside the package shall comply with I-ET-3010.00-5140-712-P4X-001 – LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS and I-ET-3010.00-5140-712-P4X-002 – MEDIUM-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS.</p> <p>5.10.4 All electrical equipment and material shall fully comply with the documents: I-ET-3010.00-5140-700-P4X-002 – SPECIFICATION FOR ELECTRICAL MATERIAL FOR OFFSHORE UNITS, I-ET-3010.00-5140-700-P4X-007 – SPECIFICATION FOR GENERIC ELECTRICAL EQUIPMENT FOR OFFSHORE UNITS, I-ET-3010.00-5140-700-P4X-009 – GENERAL REQUIREMENTS FOR ELECTRICAL MATERIAL AND EQUIPMENT FOR OFFSHORE UNITS, and I-ET-3010.00-5140-741-P4X-004 – SPECIFICATION FOR LOW-VOLTAGE GENERIC ELECTRICAL PANELS FOR OFFSHORE UNITS.</p> <p>5.10.5 Power lighting and grounding installations inside the package shall comply with requirements of I-ET-3010.00-5140-700-P4X-001 – SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS, I-ET-3010.00-5140-700-P4X-003 – ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS, and I-DE-3010.00-5140-700-P4X-003 – GROUNDING INSTALLATION TYPICAL DETAILS.</p> <p>5.10.6 Interfaces of the Package with Electrical System shall comply with I-ET-3010.00-5140-797-P4X-001 – ELECTRICAL SYSTEM AUTOMATION ARCHITECTURE, I-DE-3010.00-5140-797-P4X-002 – ELECTRICAL SYSTEM AUTOMATION TYPICAL ACTUATION DIAGRAMS, and I-LI-3010.00-5140-797-P4X-001 – ELECTRICAL SYSTEM AUTOMATION INTERFACE SIGNALS LIST.</p> <p>5.11 TELECOMMUNICATIONS</p> <p>5.11.1 Design of PAGA equipment shall fulfill the requirements, including standards and documents referred herein as well as referenced data sheets. PAGA installations and interfaces shall comply with requirements of:</p> <p>A. I-ET-3010.00-5518-767-PPT-002 - TOPSIDES PUBLIC ADDRESS SYSTEM</p> <p>B. I-MD-3010.00-5510-760-PPT-001 - GENERAL CRITERIA FOR TELECOMMUNICATIONS DESIGN</p> <p>C. I-ET-3010.2D-1350-196-P4X-001 - ERGONOMICS REQUIREMENTS FOR TOPSIDES</p> <p>5.11.2 Package shall be delivered with PAGA horns and cables installed and tested based on detail design done by SELLER.</p> <p>5.11.3 SELLER shall be responsible for the design, supplying, installation and integration of the PAGA System items of its package, complying with all applicable requirements described in I-ET-3010.00-5518-767-PPT-002 - TOPSIDES PUBLIC ADDRESS SYSTEM for the entire system.</p>			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 17 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP
<p>5.11.4 Since the PAGA network inside package to be designed is part of the entire system that is scope of SELLER detail design, SELLER shall ask BUYER any specific characteristics of the system, as well as the approval of the sound calculation memory and detailed design, to assure fully interoperability.</p> <p>5.11.5 The acoustic horns and cables shall be designed by SELLER in 02 (two) different and independent groups A and B. Each of these groups shall be ended inside a proper interface box to be installed at the edge of the package, in accordance with the classifications zone and groups established by IEC / ABNT and SELLER.</p> <p>5.11.6 SELLER shall be responsible for commissioning the PAGA network inside the package of its own scope of supply before the lifting of the package, when the system will be accepted by BUYER.</p> <p>5.11.7 SELLER shall supply all needed facilities to test the PAGA network inside package before lifting.</p> <p>5.11.8 Wherever there are closed areas in package module, they shall also be covered by UHF, LTE, and WLAN systems. So, SELLER shall make available MCT (Multi cable and pipe transit) for cables entrance and internal fixing supports for internal UHF and LTE antennas and their RF cables and industrial access points with their fiber optic cable and electrical cable. Such equipment and cables will be delivered by SELLER according to its detail design, if required.</p> <p>5.11.9 Since the UHF Active Repeater, LTE and WLAN Systems are part of complete systems scope of SELLER, SELLER shall ask the BUYER any specific characteristics of infrastructure required and detailed design to assure interoperability and functionality inside closed areas of packages module.</p> <p>5.12 INSTALLATION REQUIREMENTS</p> <p>5.12.1 Skid Details</p> <p>This section is only applicable for equipment that is built on a skid:</p> <ul style="list-style-type: none"> A. The skid shall be designed to accommodate the entire equipment within the scope of supply. The skid shall be of rigid construction, which will not distort during hoisting, operation and shipment and shall withstand all moments and forces due to the vessel motion. B. All equipment shall be installed by SELLER over structural steel deck plate in position shown in I-DE-3010.2D-1422-942-P4X-001 – M-11 – WATER INJECTION AND SULPHATE REMOVAL UNIT – EQUIPMENT LAYOUT PLAN. C. All piping terminations shall be flanged. D. The set of equipment and their skids must be designed, arranged and assembled in such a way to allow the safe personnel access, operation, and maintenance. E. Lifting facilities shall enable lifting of the equipment with crane as a single point lift for transportation and installation. The design and manufacture of the lifting lugs shall be certified. The arrangement of equipment, piping and superstructure shall be such that the center of gravity coincides approximately with the geometrical center of the skid When lifting the skids, complete with all equipment mounted, beam deflection shall not exceed 1/400 L. 			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 18 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

F. The skid shall resist all sling forces, including both horizontal and vertical components of the applied sling angle (sling angles shall be within between 50° and 90° with the horizontal plane).

G. Lifting beams, spreader bars, slings, shackles, etc. are within SELLER's scope of supply.

H. Drip trays with drain connections shall be provided underneath equipment where significant spillage is likely to occur.

I. The skid shall be welded to the supporting structures. Skid floor shall be made of plate material with a raised on-slip tread. Welds underneath skid beams shall be ground flush. Skid shall have two diagonally opposed earthing bars.

5.12.2 Maintenance Lifting Beams

A. All required maintenance lifting beams, complete with the necessary hoisting and lifting gear, shall be provided to facilitate safe and easy maintenance.

B. All lifting beams shall overhang by at least 1.2 m into agreed lay-down areas.

C. The deflection of the maintenance crane/hoisting beams shall not exceed 1/500 of the span length.

D. All beams and lifting gear shall be subject to load testing, witnessed by BUYER representative and CLASS.

5.13 PAINTING

5.13.1 Painting requirements shall be according to I-ET-3010.00-1200-956-P4X-002 – GENERAL PAINTING.

5.13.2 Color code adopted shall be in accordance with DR-ENGP-I-1.15 – COLOR CODING.

6 NAMEPLATES

6.1 GENERAL

6.1.1 SELLER shall attach corrosion resistant stainless steel type 316 nameplates on each item of equipment in an accessible location, fastened with corrosion resistant stainless steel type 316 pins, and in Portuguese language.

6.1.2 For pressure vessels, columns and filters the nameplates shall be according to I-ET-3010.00-1200-540-P4X-001 – REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION.

6.1.3 For the other equipment the nameplates shall include, as a minimum, the following information:

A. Petróleo Brasileiro S.A. – PETROBRAS;

B. Purchase order number;


C. Manufacturer and year of build;

D. Tag number;

E. Service;

F. Serial number;

G. Main data for design, operation and testing (Power, Pressure, Volume, Temperature, Rotation, Flow rate), where applicable;

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	
		SHEET	19 of 24
		INTERNAL	
		ESUP	

H. Specific requirements;
 I. Installation identification;
 J. Driver power rating and speed, where applicable;
 K. Design code;
 L. Empty weight;
 M. NR-13 information (if applicable).

6.1.4 Valves, instruments and orifices shall be tagged with the applicable number only.

7 TAG NUMBERING

7.1 GENERAL

7.1.1 Tagging of all instruments, electrical, telecommunication, mechanical and piping items, including valves, shall be in accordance with the latest revision of I-ET-3000.00-1200-940-P4X-001 – TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN.

7.1.2 For main item tag numbers, refer to I-FD-3010.2D-1251-560-P4X-003 – VACUUM DEAERATION UNIT (UT-1251003).

7.1.3 Tag numbers for remaining ancillary equipment shall be given after purchase order placement.

8 CERTIFICATION REQUIREMENTS

8.1 CLASSIFICATION SOCIETY CERTIFICATION

8.1.1 SELLER shall provide a CLASS Certificate of Compliance for the entire Unit.

8.1.2 In order to obtain the Certificate of Compliance all related CLASS activities and CLASS technical requirements are within the SELLER scope of work, as well as the all cost associated with it.

8.2 HAZARDOUS AREAS CERTIFICATION

8.2.1 All materials and equipment proper to be used in hazardous areas, shall have conformity certificates complying with: the latest revision of IEC 60079 and all its parts; PORTARIA INMETRO Nº 115 (march 21st, 2022); and shall be approved by CLASS.


9 REPAIR


9.1 GENERAL

9.1.1 Welding repairs and heat treatments must be recorded and submitted for BUYER's approval.

10 INSPECTION, TESTING AND COMMISSIONING

10.1 GENERAL

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 20 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP
<p>10.1.1 SELLER is required to propose a program for inspection and testing of all supplied equipment for approval by BUYER, prior to commencement of work in accordance with document schedule. ITP shall be issued for the equipment that are part of the Unit.</p> <p>10.1.2 Unless otherwise stated, all inspections and tests shall be performed at the workshop of SELLER in the presence of BUYER representative and CLASS surveyor as applicable.</p> <p>10.1.3 Inspections and tests are an integral part of the order which will not be considered complete until such inspections and tests have been carried out in full and recorded in an inspection report that shall be part of data book.</p> <p>10.1.4 BUYER shall issue an Inspection Release Certificate (IRC) only after completion of all required inspections and tests and after the manufacturing data books have been issued and approved.</p> <p>10.2 PERSONNEL QUALIFICATION AND CERTIFICATION</p> <p>10.2.1 Personnel qualification and certification shall be in accordance with I-ET-3010.00-1200-970-P4X-003 - REQUIREMENTS FOR PERSONNEL QUALIFICATION AND CERTIFICATION.</p> <p>10.3 QUALITY AND INSPECTION</p> <p>10.3.1 SELLER shall provide documented schedules with the estimated completion dates. These schedules shall be issued by the same time the drawings are submitted for approval, as indicated in the agreed document schedule.</p> <p>10.3.2 BUYER reserves the right to inspect all items at any time during fabrication to ensure that the materials and workmanship are in accordance with this specification and all applicable documentation.</p> <p>10.3.3 SELLER is responsible for the overall compliance of the Unit when it comes to the CLASS requirements, including certificates, work examinations and tests, as well as final inspection activities and shipment.</p> <p>10.3.4 In addition to BUYER inspection, equipment such as valves and fittings, etc. shall be subject to all CLASS authority and may range from a review of SELLER's quality manual to a physical survey of SELLER's shop or end products.</p> <p>10.3.5 The CLASS inspector shall have the right to request inspections or examinations to ensure that the equipment complies with the relevant CLASS requirements. If examination reveals any deficiencies, SELLER shall bear the full cost of repair or replacement when necessary. Any repair work shall be approved by BUYER. The subsequent examination necessary to ensure the satisfactory manufacture of the equipment in question will be on behalf of the SELLER.</p> <p>10.3.6 Except if approved by BUYER inspector, all equipment shall be presented for inspection in an unpainted state. SELLER shall provide notice to the inspector to witness the specified tests at least 2 (two) weeks in advance for Brazilian manufacturer and 3 (three) weeks for foreign manufacturer.</p> <p>10.3.7 Manufacturing Survey Inspection shall be performed according to I-ET-3010.00-</p>			

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	
		SHEET 21 of 24	
		INTERNAL	
		ESUP	

1200-972-P4X-006 - REQUIREMENTS FOR MANUFACTURING SURVEY INSPECTION.

10.3.8 Traceability of material shall comply with I-ET-3010.00-1200-978-P4X-005 - REQUIREMENTS FOR MATERIALS TRACEABILITY.

10.3.9 Equipment, piping and accessories under scope of NR-13 shall comply with I-ET-3010.00-1200-970-P4X-013 - COMPLIANCE WITH NR-13 AND SPIE REQUIREMENTS.

10.4 WELDING AND WELDING INSPECTION

10.4.1 All equipment (such as pressure vessels, filters, tanks, heat exchangers, pump, turbomachinery etc.), structures, valves and piping weldments shall be according to the requirements stated in I-ET-3010.00-1200-955-P4X-001 – WELDING.

10.4.2 Welding shall be carried out with procedures and welders qualified in accordance with Design Code and additional requirements stated in contractual technical specifications. Welding shall not be performed before qualified welding procedures specification have been approved.

10.4.3 Intermittent fillet welds are not permitted.

10.4.4 Welding inspection shall be according to the Design Code and additional requirements stated in the contractual technical specification, such as I-ET-3010.00-1200-200-P4X-115 – REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING, I-ET-3010.00-1200-540-P4X-001 – REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION, I-DE-3010.00-1400-140-P4X-004 – GENERAL NOTES FOR TOPSIDES STRUCTURES, etc.

10.5 NON DESTRUCTIVE TEST

10.5.1 NDT shall be according to the respective design Code and I-ET-3010.00-1200-970-P4X-004 - NON-DESTRUCTIVE TESTING REQUIREMENTS FOR METALLIC AND NON-METALLIC MATERIALS

10.5.2 Final NDTs, for acceptance purposes shall be carried out after completion of any post weld heat treatment (when applicable) and prior to paint application, hydrostatic testing, etc.

10.6 TESTING


10.6.1 The following tests shall be included in SELLER's scope:

- A. Pressure test (usually hydrostatic) of all vessels, heat exchangers, tanks and piping/valves;
- B. Electrical insulation and continuity checks on all wiring and earthing;
- C. Functional checks on all instruments and valves.

10.6.2 Hydrostatic testing shall be carried out in the presence of BUYER inspectors and shall include all pressure vessels, heat exchangers and applicable piping/valves.

10.6.3 All piping systems and equipment shall be drained and dried after hydrostatic testing.

10.6.4 Preservation to be applied shall be as detailed in I-ET-3010.00-1200-200-P4X-115 –

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 22 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING.

10.7 ELECTRICAL

10.7.1 The following testing shall be carried out in the presence of BUYER inspectors and shall include:

- A. Insulation (MEGGER) test for cables, electric motors and electric panels shall be provided;
- B. Tests stated in the respective motors and power/control panel specifications.

10.8 PACKAGE INSPECTION

10.8.1 Unless waived by BUYER, the following inspections and checks shall be witnessed by BUYER inspector:

- A. Verification of equipment construction materials (vessels, heat exchangers, pumps, etc.) for conformity with the specification requirements;
- B. Verification of piping, fittings and valves conform to specification of materials and fabrication;
- C. Reports for all NDT performed on the pressure retaining parts (radiographic, dye penetrant, magnetic particles, and ultrasonic inspection);
- D. Approval of the relief valve settings and witness of their testing after setting;
- E. Review of Inspection and Test Records;
- F. A visual check noting:
 - That the thickness of the pressure retaining parts meets or exceeds the quoted design thickness;
 - Any repairs;
 - Dry-film thickness of applied coatings;
 - The general appearances, materials, workmanship and standard of finish;
 - Dimensional check;
 - Alignment to be demonstrated.

10.9 PACKAGE TEST

10.9.1 A full function test of completed package shall be performed. The satisfactory operation of all indicators, selectors and controllers shall be demonstrated.


10.9.2 The correct operation of all controllers, alarm and fault protection equipment and indicators shall be demonstrated and if necessary, fault simulations.

10.9.3 SELLER shall submit a FAT procedure with a test schedule covering all items within the scope of supply.

10.9.4 SELLER shall prepare a FAT procedure for the package and submit for BUYER approval.

10.9.5 FAT will be witnessed by BUYER representatives. SELLER shall advise BUYER of the test schedule at least 2 (two) weeks for Brazilian manufacturers /Sub-Suppliers and 3 (three) weeks for foreign manufacturers/Sub-Suppliers before the planned test dates. SELLER shall invite CLASS surveyor for FAT.

10.9.6 Acceptance of the FAT will not be considered as the final acceptance test of the

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 23 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL
			ESUP

package.

10.10 ASSEMBLY ASSISTANCE AND COMMISSIONING REQUIREMENTS

10.10.1 SELLER is responsible for assembly supervision of the equipment, including the assembly of components to be delivery as loose parts (for example, some components of the pumps, like stuffing box; some internals of pressure vessels, etc.).

10.10.2 SELLER is responsible for pre-commissioning and commissioning supervision of the equipment/system. Final acceptance shall be on satisfactory completion of commissioning tests as specified by BUYER.

10.10.3 An Initial Service Safety Inspection shall be performed on the piping and on the static equipment of the Unit (pressure vessels, heat exchangers, and so on) once the Unit itself has been erected to its final location.

10.10.4 Requirements of I-ET-3010.00-1200-200-P4X-115 – REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING shall be attended.

11 SELLER RESPONSIBILITY


11.1 GENERAL

11.1.1 SELLER shall assume sole contractual and total engineering responsibility for the package equipment.

11.1.2 SELLER's responsibility shall also include, but is not limited to:

- A. Technical responsibility for the entire scope of supply;
- B. Resolving all engineering questions and/or problems relating to design and manufacture;
- C. All coordination with manufacturers and collection of all details, drawings, calculations, and data to achieve optimum design and full submission of the documents requested in the specification;
- D. Providing details as requested of any sub-vendors relating to design and manufacture;
- E. To submit to the certifying authority the documentation as described in the latest edition of their rules for equipment on offshore facilities;
- F. Installation at site by others, however, presence of supervision will be required;
- G. SELLER's responsibility shall also include Commissioning & Training for operation;
- H. Pre-Commissioning;
- I. Attend HAZOP meetings arranged by BUYER.

11.1.3 Any exclusion and/or alternative to what is specified in this Technical Specification, including the use of the SELLER's standard and exclusive technology, shall be presented in a Deviation List, subject to BUYER acceptance during the clarification phase, preceding the proposal presentation. Otherwise the requirements herein will be considered as "Agreed", and so required.

	TECHNICAL SPECIFICATION	Nº I-ET-3010.2D-1251-560-P4X-002	REV. 0
	AREA:	ATAPU 2 AND SÉPIA 2	SHEET 24 of 24
	TITLE:	VACUUM DEAERATION UNIT (UT-1251003)	INTERNAL ESUP

12 PREPARATION FOR SHIPMENT

12.1 MARKING

12.1.1 All items supplied to this specification shall be adequately marked for identification against a certificate or relevant test documentation. Marking shall be such that it will not damage or impair the component.

12.1.2 Items that cannot be identified shall be rejected. Rejected items may be re-certified by carrying out all relevant testing, with prior approval of BUYER.

12.2 SHIPMENT PACKING

12.2.1 Shipment packing preparation of the equipment shall be suitable for 24 months of outdoor storage from time of shipment.

12.2.2 All open ends of tubes on the equipment shall be treated and closed off by plastic caps and taped. Small bore threaded connections shall be taped over.

12.2.3 All carbon steel vessels, etc. shall be protected with corrosion inhibitor prior to shipment.

12.2.4 The package shall be protected from corrosion.

12.2.5 Vulnerable instruments shall be removed and packed separately for shipment.

12.2.6 Transportation bracing/support shall be used where necessary and shall be clearly identified as temporary.

12.2.7 All crates and boxes will contain sufficient moisture absorbing agent to avoid condensation.

12.2.8 SELLER shall specify any limitations applicable to the transport and installation phase.