 PETROBRAS	TECHNICAL SPECIFICATION		Nº: I-ET-3010.2Q-5300-312-P4X-001
	CLIENT:	MARLIM LESTE E SUL	SHEET: 1 of 16
	JOB:	BASIC DESIGN – REVIT I	
	AREA:	MARLIM LESTE E SUL	
	TITLE:	PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)	ESUP
MICROSOFT WORD / V. 2019 / I-ET-3010.2Q-5300-312-P4X-001_B.DOCX			INTERNAL

INDEX OF REVISION

REV.	DESCRIPTION AND/OR REVISED SHEETS
0	ORIGINAL
A	REVISED WHERE INDICATED
B	REVISED WHERE INDICATED

	REV. 0	REV. A	REV. B	REV. C	REV. D	REV. E
DATE	SEP/19/23	JUN/11/24	JUN/14/24			
EXECUTION	CLYZ	U4XP	CLYZ			
CHECK	U4XP	CLYZ	HR7O			
APPROVAL	CXM6	EGKA	EGKA			

THE INFORMATION CONTAINED IN THIS DOCUMENT IS PETROBRAS' PROPERTY AND MAY NOT BE USED FOR PURPOSES OTHER THAN THOSE SPECIFICALLY INDICATED HEREIN. THIS FORM IS PART OF PETROBRAS' NI-381-REV.M.



TITLE: PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)

ESUP

INTERNAL

SUMMARY

1 INTRODUCTION.....4

1.1 OBJECTIVE.....4

1.2 DEFINITIONS4

1.3 ABBREVIATIONS4

2 NORMATIVE REFERENCES4

2.1 INTERNATIONAL CODES, RECOMMENDED PRACTICES AND STANDARDS....4

2.2 BRAZILIAN CODES AND STANDARDS5

2.3 CLASS APPROVAL AND CERTIFICATION.....5

3 REFERENCE DOCUMENTS5

4 DESIGN REQUIREMENTS.....7

4.1 DESIGN CONDITIONS7

4.2 SAFETY REQUIREMENTS8

4.3 NOISE AND VIBRATIONS8

4.4 MOTIONS AND ACCELERATION8

5 PACKAGE SCOPE OF SUPPLY9

5.1 SCOPE OF SUPPLY9

5.2 EQUIPMENT LOCATION9

6 PACKAGE SPECIFICATION.....10

6.1 GENERAL.....10

7 GENERAL REQUIREMENTS.....10

7.1 INSTRUMENTATION AND AUTOMATION REQUIREMENTS.....10

7.2 PAINTING REQUIREMENTS11

7.3 MECHANICAL, PIPING AND ACCESSORIES11

7.4 AVAILABLE ON BOARD11

7.5 NAMEPLATES AND TAG NUMBERING11

7.6 GROUNDING REQUIREMENTS.....11


8 PACKAGE MANUFACTURING12

8.1 GENERAL.....12

8.2 QUALITY ASSURANCE AND CONTROL SYSTEM.....12

8.3 WELDING AND NDT12

8.4 INSPECTION AND TESTS12

	TECHNICAL SPECIFICATION	I-ET-3010.2Q-5300-312-P4X-001	REV.: B
			SHEET: 3 of 16
	TITLE: PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)		ESUP
			INTERNAL
8.5 FACTORY ACCEPTANCE TEST (FAT)..... 13 8.6 PRE-COMMISSIONING AND COMMISSIONING 14 9 PACKAGE DELIVERY REQUIREMENTS..... 14 9.1 PRESERVATION, PACKING AND TRANSPORTATION 14 9.2 SPARE PARTS, CONSUMABLES AND TOOLS..... 15 9.3 DOCUMENTATION 15			



TITLE: PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)

ESUP

INTERNAL

1 INTRODUCTION

1.1 OBJECTIVE

The purpose of this technical specification is to describe the minimum requirements for the design, manufacturing, assembly, supply, installation, commissioning, and tests of PNEUMATIC PUMPS FOR HULL SYSTEMS PACKAGE in conformance with relevant regulations and Marlim Leste e Sul – REVIT I basic design documentation.

1.2 DEFINITIONS

PACKAGE: It is defined as an assembly of equipment supplied interconnected, tested and ready to operate, requiring only the available utilities from the Unit for the Package operation.

PACKAGER: It is defined as the responsible for project, assembly, construction, fabrication, testing and furnishing of the Package.

PNEUMATIC PUMPS FOR HULL SYSTEMS PACKAGE: It is the package name.

BUYER: PETROBRAS.

All definitions are found on I-ET-3010.00-1200-940-P4X-002 – GENERAL TECHNICAL TERMS.

1.3 ABBREVIATIONS

CS	Classification Society
FAT	Factory Acceptance Tests
FPSO	Floating Production Storage and Offloading Unit
SOS	Supervisory and Operation System
SOS-HMI	Human Machine Interface of SOS

2 NORMATIVE REFERENCES

2.1 INTERNATIONAL CODES, RECOMMENDED PRACTICES AND STANDARDS

The equipment will be designed and manufactured in accordance with the following codes and standards, if not mentioned otherwise.

- ANSI American National Standards Institute
- API American Petroleum Institute
- ASME American Society of Mechanical Engineers
- BGV German Safety Regulations
- DIN German National Standard Code
- EN European Standards
- ISO International Standard Organization
- IMO – International Maritime Organization
- IMO Resolution MEPC 107 (49)
- MARPOL
- SOLAS II-1, Regulation 3-5, and MSC.1/Circ. 1379



TITLE: **PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)**

ESUP

INTERNAL

- VDE / IEC German National Electric Standard Codes / International Electric Codes
- IEC 61892, INMETRO Resolution 179, May 18th 2010 and INMETRO resolution 89, February 23rd 2012
- Classification Society defined for the Hull scope.

2.2 BRAZILIAN CODES AND STANDARDS

- NR – Brazilian Federal Government Regulatory Norms (Normas Regulamentadoras NRs)
- NORMAM-01 – Normas da Autoridade Marítima para Embarcações Empregadas na Navegação em Mar Aberto;

2.3 CLASS APPROVAL AND CERTIFICATION

PACKAGE shall be designed, manufactured and tested according to the design reference documents, normative requirements and in accordance with the latest editions of Classification Society Rules, Regulations and Standards

3 REFERENCE DOCUMENTS

REF DOC NUMBER	REF DOC NAME
GENERAL	
I-DE-3010.2Q-1200-942-P4X-002	GENERAL ARRANGEMENT
I-DE-3010.2Q-1200-94A-P4X-001	AREA CLASSIFICATION – GENERAL
I-ET-3000.00-0000-940-P4X-002	SYMBOLS FOR PRODUCTION UNITS DESIGN
I-ET-3000.00-1000-941-PPC-001	METOCEAN DATA
I-ET-3000.00-1200-940-P4X-001	TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN
I-ET-3010.00-1200-940-P4X-002	GENERAL TECHNICAL TERMS
I-RL-3010.2Q-1200-940-P4X-001	GENERAL SPECIFICATION FOR AVAILABLE UTILITIES
CONSTRUCTION	
I-ET-3010.00-1200-955-P4X-001	WELDING
I-ET-3010.00-1000-970-P4X-002	REQUIREMENTS FOR NDT
I-ET-3010.00-1200-955-P4X-002	REQUIREMENTS FOR WELDING INSPECTION



TECHNICAL SPECIFICATION

I-ET-3010.2Q-5300-312-P4X-001

REV.: **B**

SHEET: 6 of 16

TITLE: **PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)**

ESUP

INTERNAL

I-ET-3010.00-0000-970-P4X-001	REQUIREMENTS FOR PROCEDURES AND PERSONNEL QUALIFICATION AND CERTIFICATION
HULL SYSTEMS	
I-DE-3010.2Q-5320-944-P4X-001	UPPER RISER BALCONY DRAINAGE SYSTEM
I-DE-3010.2Q-5330-944-P4X-002	HULL EXPOSED AREAS DRAINING SYSTEM
I-DE-3010.2Q-5330-944-P4X-003	COFFERDAM, VOID SPACES AND STORES DRAINING SYSTEM
I-FD-3010.2Q-5320-312-P4X-001	UPPER RISER BALCONY PNEUMATIC DRAINAGE PUMPS (B-5320501A/D)
I-FD-3010.2Q-5320-312-P4X-003	PORTABLE PNEUMATIC DRAINAGE PUMPS (B-5330507A/B)
I-FD-3010.2Q-5320-312-P4X-004	COFFERDAM PNEUMATIC DRAINAGE PUMPS (B-5330510A/B)
I-FD-3010.2Q-5320-312-P4X-002	FORE CASTLE AND FWD/AFT OFFLOADING STATION DRAINAGE PNEUMATIC PUMPS (B-5330512A/B, B-5330505, B-5330506)
I-MD-3010.2Q-1200-940-P4X-027	DESCRIPTIVE MEMORANDUM - HULL SYSTEMS
NAVAL	
I-DE-3010.2Q-1350-960-P4X-002	CAPACITIES PLAN
I-ET-3010.00-1350-960-P4X-002	DESIGN REQUIREMENTS - NAVAL ARCHITECTURE
I-RL-3010.2Q-1350-960-P4X-002	MOTION ANALYSIS
MECHANICAL	
I-ET-3010.00-1200-300-P4X-001	NOISE AND VIBRATION CONTROL REQUIREMENTS
PAINTING	
I-ET-3010.00-1200-956-P4X-002	GENERAL PAINTING
DR-ENGP-I-1.15	COLOR CODING
SAFETY	

DR-ENGP-M-I-1.3	SAFETY ENGINEERING GUIDELINE
I-ET-3010.00-5400-947-P4X-002	SAFETY SIGNALING
PIPING	
I-ET-3010.2Q-1200-200-P4X-001	PIPING SPECIFICATION FOR TOPSIDES
I-ET-3010.00-1200-251-P4X-001	REQUIREMENTS FOR BOLTING MATERIALS
ELECTRICAL	
I-DE-3010.00-5140-700-P4X-003	GROUNDING INSTALLATION TYPICAL DETAILS
I-ET-3010.00-5140-700-P4X-001	SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS
INSTRUMENTATION AND AUTOMATION	
I-ET-3010.00-1200-800-P4X-002	AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS
I-ET-3010.2Q-1200-800-P4X-014	AUTOMATION INTERFACE OF PACKAGED UNITS
I-ET-3010.00-1200-800-P4X-013	GENERAL CRITERIA FOR INSTRUMENTATION PROJECTS
I-ET-3010.00-5520-888-P4X-001	AUTOMATION PANELS

Table 1 – Reference Documents

Note: Reference Documents latest revision shall be considered.

4 DESIGN REQUIREMENTS

4.1 DESIGN CONDITIONS

4.1.1. PACKAGE Equipment shall be designed for a 25-year life in a corrosive offshore environment without the need for replacement of any major component due to wear, corrosion, fatigue, or material failure.

4.1.2. PACKAGER shall design the equipment for the full range of operational conditions as specified in this technical specification.

4.1.3. PACKAGE Equipment shall be designed with the compliance of the normative and design requirements as stated in this specification and complying with the technical parameters stated on the above item 3 with the Marlim Leste e Sul – REVIT I design reference documents.

4.1.4. All elements of the PACKAGE shall be of proven design and well within the manufacturer's actual experience.

4.1.5 PACKAGE shall be designed in compliance with ISO 80079-36 and ISO 80079-37

TITLE: **PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)****ESUP****INTERNAL**

requirements.

4.1.5.1 PACKAGER shall provide a certificate confirming that the equipment and components of the package is in conformity with both standards including as minimum:

- a) Ignition Hazard Assessment Report as per ISO 80079-36;
- b) Specific requirements for the design and construction of nonelectrical and equipment type of protection as per ISO 80079-37;
- c) Equipment nameplate including ISO 80079-36 marking requirements.

4.1.5.2 PACKAGER shall attest on his own responsibility that the equipment has been constructed in accordance with the applicable requirements of the relevant standards in safety matters.

4.2 SAFETY REQUIREMENTS

4.2.1. Personnel safety protection shall be provided according to Brazilian Regulatory Norms (NR) issued by Brazilian Government.

4.2.2. Warning signs in Brazilian Portuguese language shall be provided where risk of personnel injury exist.

4.2.3. Rotating equipment outer parts, such as pulleys, couplings, belts and flywheels, shall have rigid protection, manufactured with aluminum ASTM B211 and shall be capable of being easily removed.

4.2.4. In accordance with the requirements of SOLAS II-1, Regulation 3-5, and MSC.1/Circ. 1379, all equipment and material to be supplied by PACKAGER shall "asbestos free".

4.2.5. Safety signaling shall be in full compliance with I-ET-3010.00-5400-947-P4X-002 – SAFETY SIGNALING.

4.2.6. Double block & bleed arrangements are required for isolation of equipment in piping classes of 300# and above.

4.2.7. PACKAGER shall comply with the requirements of NR-13 (Brazilian Government Regulation) on design and fabrication of all PACKAGE equipment or piping that stands under NR-13 norm and shall provide all corresponding documents.

4.3 NOISE AND VIBRATIONS

4.3.1. Noise and vibrations limits shall be in conformance with I-ET-3010.00-1200-300-P4X-001 – NOISE AND VIBRATION CONTROL REQUIREMENTS.

4.4 MOTIONS AND ACCELERATION

4.4.1. All equipment shall be able to withstand with the UNIT subjected to 100-year return period environmental conditions.

4.4.2. All equipment shall be able to operate with the UNIT subjected to 1-year return period environmental conditions.

4.4.3. All environmental conditions are defined in I-ET-3000.00-1000-941-PPC-001 – METOCEAN DATA, at any draft from fully loaded to the minimum loaded / ballasted condition.

4.4.4. For the Hull loading conditions details and the maximum designed operational trim and heel inclinations refer to I-ET-3010.00-1350-960-P4X-002 – DESIGN REQUIREMENTS - NAVAL ARCHITECTURE.

4.4.5. For the design data and information regarding motion requirements refer to I-RL-3010.2Q-1350-960-P4X-002 – MOTION ANALYSIS.

4.4.6. PACKAGE is also to withstand inertial forces during transportation from construction site to the final offshore location.

5 PACKAGE SCOPE OF SUPPLY

5.1 SCOPE OF SUPPLY

5.1.1. PACKAGE shall be supplied as the following minimum components:

	TAG	Description	Qty
1	B-5320501A/D	Upper Riser Balcony Drainage Pump	4
2	B-5330505	FWD Offloading Station Drainage Pneumatic Pump	1
3	B-5330506	AFT Offloading Station Drainage Pneumatic Pump	1
4	B-5330507 A/B	Portable Pneumatic Pumps For Hull Drainage	2
5	B-5330510A/B	Cofferdam Pneumatic Drainage Pumps	2
6	B-5330512A/B	Fore Castle Pneumatic Drainage Pumps	2

Table 2 – Scope of Supply

5.1.2. Pneumatic pumps shall be completed with at least the following components and accessories:

- a. One filter and pressure regulator with pressure gauge for each pump on the compressed air inlet. These components' details to be confirmed according to pumps manufacturer requirements (HULL SUPPLIER scope of supply).
- b. It shall be defined in the Detailed Design Phase if the pneumatic pumps require any protection against overpressure (blocked discharge). To be confirmed according to pumps manufacturer requirements.

5.1.3. All other parts or components required for safe and suitable operation of the system.

5.2 EQUIPMENT LOCATION

5.2.1. Pneumatic pumps shall be located on the Unit Hull Cargo Area and Upper Riser Balcony as the following table:

TAG	Description	Location
B-5320501A/D	Upper Riser Balcony Drainage Pump	Upper riser balcony
B-5330505	FWD Offloading Station Drainage Pneumatic Pump	Fwd offloading station
B-5330506	AFT Offloading Station Drainage Pneumatic Pump	Aft offloading station

B-5330507A/B	Portable Pneumatic Pumps For Hull Drainage	Main Deck
B-5330510A/B	Cofferdam Pneumatic Drainage Pumps	Cofferdam (TQ-1358508), between Slop Tanks
B-5330512A/B	Fore Castle Pneumatic Drainage Pumps	Forecastle

Table 3 – Pumps Location

5.2.2. For Equipment Location refer to I-DE-3010.2Q-1200-942-P4X-002 – GENERAL ARRANGEMENT and I-DE-3010.2Q-1200-94A-P4X-001 – AREA CLASSIFICATION - GENERAL.

6 PACKAGE SPECIFICATION

6.1 GENERAL

6.1.1. Pumps shall be specified as the below references:

TAG	Reference Document
B-5320501A/D	I-FD-3010.2Q-5320-312-P4X-001
B-5330505, B-5330506, B-5330512A/B	I-FD-3010.2Q-5320-312-P4X-002
B-5330507A/B	I-FD-3010.2Q-5320-312-P4X-003
B-5330510A/B	I-FD-3010.2Q-5320-312-P4X-004

Table 4 – Pumps Specification

6.1.2. PACKAGE shall be designed for continuous operation at full load duty, unless otherwise stated in the process data sheets.

6.1.3. PACKAGE shall be connected, wired and supplied as a complete unit, ready for installation and operation.

7 GENERAL REQUIREMENTS


7.1 INSTRUMENTATION AND AUTOMATION REQUIREMENTS

7.1.1. PACKAGE shall be protected with all necessary instruments to operate safely, adequately and without interruption in a tropical marine environment.

7.1.2. The instrumentation and control design shall fulfill the requirements of the following technical specifications:

- i. I-ET-3010.00-1200-800-P4X-002 – AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS.
- ii. I-ET-3010.00-1200-800-P4X-013 – GENERAL CRITERIA FOR INSTRUMENTATION PROJECTS.

7.1.3. The minimum requirements for the adequate interfacing of the PACKAGE Automation and Instrumentation System with the UNIT are described on I-ET-3010.2Q-1200-800-P4X-014 –

	TECHNICAL SPECIFICATION	I-ET-3010.2Q-5300-312-P4X-001	REV.: B
			SHEET: 11 of 16
	TITLE: PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)		ESUP
			INTERNAL

AUTOMATION INTERFACE OF PACKAGE UNITS.

7.1.4. For the control and automation panels design requirements I-ET-3010.00-5520-888-P4X-001 – AUTOMATION PANELS shall be considered.

7.2 PAINTING REQUIREMENTS

7.2.1. Painting and coating in accordance with I-ET-3010.00-1200-956-P4X-002 – GENERAL PAINTING and DR-ENGP-I-1.15 COLOR CODING.

7.2.2. All components shall be delivered fully painted/coated, unless otherwise indicated on this specification.

7.2.3. The performed pre-treatment and complete coating shall be in accordance with the paint manufacturer's data sheets.

7.3 MECHANICAL, PIPING AND ACCESSORIES

7.3.1. All PACKAGE interconnection piping shall comply with the requirements of ASME B31.3.

7.3.2. PACKAGE piping and accessories of the skid mounted equipment shall be in accordance with the specification ASME B31.3.

7.3.3. Piping flanges according to the ASME B16.5.

7.3.4. For Hull piping and valves specification refer to I-ET-3010.2Q-1200-200-P4X-001 – PIPING SPECIFICATION FOR TOPSIDES.

7.3.5. For bolts and nuts refer to I-ET-3010.00-1200-251-P4X-001 – REQUIREMENTS FOR BOLTING MATERIALS.

7.4 AVAILABLE ON BOARD

7.4.1. For other utilities available onboard refer to I-RL-3010.2Q-1200-940-P4X-001 – GENERAL SPECIFICATION FOR AVAILABLE UTILITIES.

7.5 NAMEPLATES AND TAG NUMBERING

7.5.1. PACKAGER / MANUFACTURER Equipment shall have nameplates in Brazilian Portuguese language, made of stainless steel AISI 316L, with 3 mm minimum thickness and fixed by stainless steel (AISI 316L) bolts or fasteners on visible and accessible location.

7.5.2. Tagging of all instruments, electrical, mechanical and piping items, including valves, shall be carried out.

7.5.3. Tags shall be supplied with the number and description in the Brazilian Portuguese Language, unless otherwise stated in the technical data sheets.


7.5.4. For TAG numbering refer to I-ET-3000.00-1200-940-P4X-001 – TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN.

7.5.5. For Instrumentation tagging the ISA –5.1 and N-1710 shall be followed.

7.5.6. The pumps shall be made of metallic material.

7.6 GROUNDING REQUIREMENTS

7.6.1. Grounding installations shall comply with I-DE-3010.00-5140-700-P4X-003 – GROUNDING INSTALLATION TYPICAL DETAILS and I-ET-3010.00-5140-700-P4X-001 – SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS".

	TECHNICAL SPECIFICATION	I-ET-3010.2Q-5300-312-P4X-001	REV.: B
			SHEET: 12 of 16
	TITLE: PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)		ESUP
			INTERNAL

8 PACKAGE MANUFACTURING

8.1 GENERAL

8.1.1. All materials and equipment supplied by PACKAGER / MANUFACTURER shall be brand new (not overhauled), field proven, free from defects and accepted by BUYER and the Classification Society.

8.1.2. Materials and equipment shall be manufactured according to internationally recognized standards for the offshore oil drilling and production industries and shall be in conformance with the Basic Design and Agreement specifications and requirements.

8.1.3. Field proven definition: Systems and equipment shall demonstrate satisfactory operation at least in 3 floating offshore installation units, operating under similar process conditions (pressure, flow, capacity and similar fluids) for a minimum of 24,000 hours. For rotating equipment, they shall demonstrate operation with fluid, flow and discharge pressure similar to the design. Unproven designs or prototypes (including components) without offshore service will not be accepted.

8.2 QUALITY ASSURANCE AND CONTROL SYSTEM

8.2.1. PACKAGER shall submit his Quality Assurance / Quality Control handbook to HULL SUPPLIER for information.

8.2.2. Engineering, fabrication and manufacturing shall conform to good manufacturing practices. Quality system according to ISO 9001 in relevant extent shall be in place and implemented.

8.3 WELDING AND NDT

8.3.1. All equipment, structures and piping welds shall be performed according to the requirements described in the latest revision of I-ET-3010.00-1200-955-P4X-001 – WELDING.

8.3.2. Welding shall be carried out with procedures and welders qualified in accordance with ASME Section IX. Welding shall not be performed before qualified welding procedures have been approved.

8.3.3. Intermittent fillet welds are not acceptable.

8.3.4. Welding inspection and NDTs shall be performed according to the requirements described in the latest revision of

- I-ET-3010.00-1000-970-P4X-002 – REQUIREMENTS FOR NDT and
- I-ET-3010.00-1200-955-P4X-002 – REQUIREMENTS FOR WELDING INSPECTION.

8.3.5. Qualification and Certification for procedures and personnel shall be in accordance with I-ET-3010.00-0000-970-P4X-001 – REQUIREMENTS FOR PROCEDURES AND PERSONNEL QUALIFICATION AND CERTIFICATION.

8.3.6. Final NDTs, for acceptance purposes shall be carried out after completion of any post weld heat treatment (when applicable) and before the applications of painting, hydrostatic testing, etc.

8.3.7. For pressure vessels, additional requirements are established in I-ET-3010.00-1200-540-P4X-001 – REQUIREMENTS FOR PRESSURE VESSEL DESIGN AND FABRICATION.

8.4 INSPECTION AND TESTS

8.4.1. PACKAGER / MANUFACTURER shall develop and implement an Inspection and Test Plan (ITP) containing hold points, review and witness points following the schedule of the PACKAGE inspections, tests and events accordingly.

TITLE: **PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)**

ESUP

INTERNAL

8.4.2. PACKAGE inspection, tests and events shall be attended by the MANUFACTURER, PACKAGER, HULL SUPPLIER, CS and BUYER inspection team whenever necessary.

8.4.3. PACKAGE shall be tested according to the design codes, applicable industry standards, CS Rules and any other one requirement stated on this technical specification.

8.4.4. Unless waive by BUYER, the following PACKAGE inspections and checks shall be witnessed by BUYER inspector:

- i. verification of equipment construction materials (vessels, heat exchangers, pumps, etc.) for conformity with the specification requirements.
- ii. verification of piping, fittings and valves conform to specification of materials and fabrication.
- iii. reports for all NDT performed on the pressure retaining parts (radiographic, dye penetrant, magnetic particles and ultrasonic inspection).
- iv. approval of the relief valve settings and witness of their testing after setting.
- v. review of Inspection and Test Records.
- vi. visual check

8.5 FACTORY ACCEPTANCE TEST (FAT)

8.5.1. FAT is a set of functional and performance tests to be executed in any equipment, electrical, instrumentation and telecom panels or any other commissionable item carried out on the PACKAGER / MANUFACTURER factory or in specialized test facilities, in order to demonstrate its compliance with the project specifications and allow its release to shipyard.

8.5.2. The Factory Acceptance Test (FAT) shall cover all the following minimum scope requirements:

- i. Pressure test (usually hydrostatic) test of all vessels, heat exchangers, tanks, pumps, pipes and valves.
 - a. Note: All piping systems and equipment shall be drained and dried after hydrostatic testing.
- ii. Performance test, NPSH test and Mechanical running test of all pumps.
- iii. Electrical continuity checks on all wiring and earthing.
- iv. Functional checks on all instruments and valves.
- v. Alarms and Equipment Protection Tests.
- vi. All other equipment tests and factory checking to be carried out according to the FAT procedure approved by parts.

8.5.3. For Factory Acceptance Test (FAT) event invitation e reports:

- i. BUYER, CS and HULL SUPPLIER shall be communicated about the FAT event following ITP and the fabrication schedule. FAT invitation schedule shall be negotiated during PACKAGE kick-off meeting on the detail design phase.
- ii. PACKAGER shall issue the FAT procedure for all parts involved as BUYER, HULL SUPPLIER and CS, where applicable, and submit to them for approval.
- iii. PACKAGER shall issue the FAT report with all test results and duly signed or stamped by all parts that witnessed the FAT and with the test reference documentation attached.
- iv. Acceptance of FAT will not be considered as the final acceptance test of the PACKAGE.

TITLE: **PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)**

ESUP

INTERNAL

8.6 PRE-COMMISSIONING AND COMMISSIONING

8.6.1. PACKAGER / MANUFACTURER shall be required to provide any necessary support for installation, assembly, pre-commissioning and commissioning of the PACKAGE either at a shore-based fabrication yard or onboard the FPSO.

8.6.2. PACKAGER / MANUFACTURER is responsible for assembly supervision of the PACKAGE equipment, including the assembly of components to be delivered loose (for example, some components of the pumps, like stuffing box, etc.).

8.6.3. Final acceptance will be on satisfactory completion of commissioning tests as specified by BUYER.

9 PACKAGE DELIVERY REQUIREMENTS

9.1 PRESERVATION, PACKING AND TRANSPORTATION

9.1.1. PACKAGER / MANUFACTURER shall ensure all the conditions and practices of preservation, packing and transportation are fulfilled and following the PACKAGE / Equipment specific and technical characteristics recommendations.

9.1.2. PACKAGER / MANUFACTURER shall submit to HULL SUPPLIER the PACKAGE preservation requirements and recommendations with all necessary considerations for the PACKAGE Equipment preservation during the UNIT whole design life.

9.1.3. Preservation and packing shall be proper for transportation and storage in a marine environment and protected against moisture and damage during transport, handling and lifting.

9.1.4. In any case, suitable preservation and protective measures shall be provided to prevent equipment deterioration prior to entering into service.

9.1.5. All packing shall be clearly marked for shipping, including lifting points, gross weight, dimensions and center of gravity.

9.1.6. All sea fastening and temporary supports used on the equipment for shipment shall be clearly identified.

9.1.7. PACKAGER / MANUFACTURER shall ensure that all loose valves, tubes and instruments are supplied with plastic caps.

9.1.8. PACKAGER / MANUFACTURER shall also ensure that all electric panels and motors will be supplied with Volatile Corrosion Inhibitor (VCI) impregnated plastic protection or similar, and external plug for space heater connection.

9.1.9. PACKAGER / MANUFACTURER shall provide clear and comprehensive instructions on the exterior of all packages advising the necessary warning notices for unpacking, handling and installing the equipment on arrival at destination.

9.1.10. The equipment shall be thoroughly cleaned internally and be free of all loose foreign materials.

- i. The preparation shall make the equipment suitable for outdoor storage in a coastal tropical climate from the time of Shipment.
- ii. If there is a risk of damage to valves and other appurtenances during transportation, they shall be disconnected and tagged. All components shall then be securely packed as above.
- iii. Spare parts and tools to be packed separately and clearly marked "Spare Parts" and "Tools" respectively.

9.2 SPARE PARTS, CONSUMABLES AND TOOLS

9.2.1. All equipment / material consumable and spare parts recommended by PACKAGER / MANUFACTURER for the construction, testing, commissioning, pre-operation and start-up phases.

9.2.2. All spare parts recommended or required by the CS, such spare parts will be delivered together with the relevant equipment.

9.2.3. All special tools required for construction, pre-commissioning, commissioning and all levels of maintenance and operation.

9.2.4. Spare parts list recommended by PACKAGER / MANUFACTURER for two years of operation.

9.3 DOCUMENTATION

9.3.1. Drawings and Weight Control


For Engineering Documentation minimum requirements:

- i. PACKAGER / MANUFACTURER design drawings shall show all necessary dimensions and details required for interface information and installation.
- ii. Clearances for maintenance shall be shown on the drawings.
- iii. Drawings and documents shall be clear and completely legible with all text in the English language.
- iv. Instruction manuals for operation and maintenance of the PACKAGE equipment shall be provided in Portuguese language.
- v. Drawings are only accepted when signed by PACKAGER as checked and approved. All revised editions of drawings or documents shall show the revisions clearly marked up, the issue date and PACKAGER's checked and approved signatures.
- vi. PACKAGER / MANUFACTURER shall produce a weight / center of gravity data sheet considering each PACKAGE component with the respective assembly dry and operational weight and CoG.
 - a. Note: Operational weight means the component dry weight added to the respective component fluid weight on operational condition.
- vii. PACKAGER shall send in advance all recommendations for PACKAGE installation, maintenance and commissioning.

9.3.2. Data Book

PACKAGER shall issue a PACKAGE / Equipment Data Book to be delivered to HULL SUPPLIER for approval. Data Book minimum content shall be as the following:

- i. Certified drawings, data sheets, technical specifications, performance curves and calculation memorandum.
- ii. Construction, maintenance and operating manuals, instructions for preservation and commissioning, and all catalogs, including of the sub-suppliers.
- iii. All certificates of materials and equipment, certificates of electrical cables and equipment to hazardous areas, all tests, destructive and non-destructive examinations, test reports (including FAT), certificates and reports of classification society, procedures for welding qualifications and welding processes.
- iv. The documentation requested by Brazilian law NR-13, subdivided for equipment (if applicable).
- v. The documentation requested by Brazilian law NR-10, subdivided for equipment (if

	TECHNICAL SPECIFICATION	I-ET-3010.2Q-5300-312-P4X-001	REV.: B
			SHEET: 16 of 16
	TITLE: PNEUMATIC PUMPS FOR HULL SYSTEMS (B-5133503, B-5320501A/D, B-5330505, B-5330506, B-5330507A/B, B-5330510A/B, B-5330512A/B)		ESUP
			INTERNAL

applicable).

Data Book delivery standard and conditions including number of parts and sections, number of printed and electronic copies will be further defined by BUYER on detail design phase.