
| | | TE | CHNICAL | SPECIFIC | CATION | No. | I-ET-3010 |).2Q-1251- | 560-P4X-0 | 03 |
|--------------------------------------|------------|----------------------|------------------------|------------------------|----------------|----------------|------------|------------|-----------|--------|
| BR | | CLIENT: | | | MARLIM | LESTE E | SUL | | SHEET: 1 | of 24 |
| | | JOB: | | E | BASIC DE | SIGN - RE | VIT I | | | - |
| PETROBRAS AREA: MARLIM LESTE E SUL | | | | | | | | | | |
| | | TITLE: | | | | | | | ES | SUP |
| SR | GE | | V | | DEAERAT | ION UNIT | (UT-1251 | 003) | - | RNAL |
| | | | | | | | | | | |
| | | | | INDE | X OF I | REVISI | ON | | | |
| REV. | | | | DESCRI | PTION AN | D/OR RE | VISED SH | EETS | | |
| 0 | ORIO | SINAL IS | SSUE | | | | | | | |
| A | RE\/ | ISED W | HERE IND | NCATED | | | | | | |
| | IXLV | IOLD VV | I ILIXL IINL | JICATED | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | DEV. C | DEV. | DEV. 5 | DEV. C | DEVI | DEV. 5 | DEV.E. | DEV. C | DEV |
| DATE | ı | REV. 0 //AR/20/24 | REV. A JUN/05/24 | REV. B | REV. C | REV.D | REV. E | REV. F | REV. G | REV. H |
| DESIGN | | ESUP | ESUP | | | | | | | |
| EXECUTION | | CJW2 | CJW2 | | | | | | | |
| CHECK | | CJX4 | HR7W | | | | | | | |
| APPROVAL INFORMATION | IN THIS DO | U32N DCUMENT IS F | CJX4 PROPERTY OF PE | TROBRAS. BEIN | G PROHIBITED O | UTSIDE OF THEI | R PURPOSE. | | | |
| FORM OWNED | | | | O D I W . O , D L II W | | O.DE OF THE | | | | |



| TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-------------------------------------|-----------------------------|----------------------|
| MARLIM LESTE E SUL | | |
| VACUUM DEAERATION UNIT (UT-1251003) | | ESUP |
| VACUUM DEAERAT | 10N 0N11 (01-1251003) | INTERNAL |

SUMMARY

| 1 | OBJECTIVE | 3 |
|---|--|----|
| 2 | NORMATIVE REFERENCES AND DESIGN SPECIFICATIONS | 3 |
| 3 | DEFINITIONS AND ABBREVIATIONS | 8 |
| 4 | PACKAGE REQUIREMENTS | 9 |
| 5 | CERTIFICATION REQUIREMENTS | 20 |
| 6 | INSPECTION, TESTING AND COMMISSIONING | 20 |
| 7 | SELLER RESPONSIBILITY | 23 |
| 8 | PREPARATION FOR SHIPMENT | 23 |



1 OBJECTIVE

This Technical Specification covers the minimum requirements for design, engineering, materials, fabrication, inspection, testing, commissioning, and pre-commissioning of the VACUUM DEAERATION UNIT (UT-1251003).

VACUUM DEAERATION UNIT (UT-1251003) shall be provided with all necessary instruments to operate safely, adequately and without interruption in an offshore facility.

The requirements herein listed apply to all players which will perform any activity related to the scope of this unit, including manufacturers, packagers, main contractor, subcontractors, suppliers, sub-suppliers, integrators, constructors, and all technical personnel involved. Within the scope of this document, they are all referred to as being a SELLER.

In addition to the requirements of this technical specification, SELLER shall follow all the requirements of the Exhibit I (SCOPE OF SUPPLY), as well as Exhibit III (DIRECTIVES FOR PRODUCT DEVELOPMENT), Exhibit IV (DIRECTIVES FOR PRODUCT FABRICATION), Exhibit V (DIRECTIVES FOR ACQUISITIONS), Exhibit VI (DIRECTIVES FOR PLANNING AND CONTROL), Exhibit VII (DIRECTIVES FOR QUALITY ASSURANCE SYSTEM) and Exhibit VIII (DIRECTIVES FOR COMMISSIONING PROCESS).

2 NORMATIVE REFERENCES AND DESIGN SPECIFICATIONS

2.1 CLASSIFICATION SOCIETY

- 2.1.1 SELLER shall perform the work in accordance with the requirements of the Classification Society.
- 2.1.2 SELLER is responsible to submit to the Classification Society the documentation in compliance with stated Rules.
- 2.1.3 Classification Society rules may only be waived upon the formal approval from the Classification Society itself and from BUYER.

2.2 CODES AND STANDARDS

- 2.2.1 The following codes and standards include provisions which, through reference in this text, constitute provisions of this specification. The latest issue of the references shall be used unless otherwise agreed.
- 2.2.2 Other recognized standards may be used, provided it can be shown that they meet or exceed the requirements of the standards referenced below. Formal approval from BUYER and from Classification Society is also required.



| | TECHNICAL SPECIFICATION No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|---|---|----------------------|
| | MARLIM LESTE E SUL | SHEET: 4 of 24 |
| 6 | TITLE: VACUUM DEAEDATION UNIT (UT 1251002) | ESUP |
| | VACUUM DEAERATION UNIT (UT-1251003) | INTERNAL |

Table 1: Codes and Standards

| AISC ASD | Steel Construction Manual | | |
|--|---|--|--|
| API RP 14C | Analysis, Design, Installation and Testing of Safety Systems for Offshore Production Facilities | | |
| API RP 14E | Recommended Practice for Design and Installation of Offshore Production Platform Piping Systems | | |
| API RP 14J | Recommended practice for Design and Hazards Analysis for Offshore Production Facilities | | |
| API RP 14FZ | Recommended Practice for Design, Installation, and Maintenance of Electrical Systems for Fixed and Floating Offshore Petroleum Facilities for Unclassified and Class I, Zone 0, Zone 1 and Zone 2 Locations | | |
| API RP 505 | Classification of locations for Electrical Installations at Petroleum Facilities Classified as Class I, Zone 0, Zone 1 and Zone 2 | | |
| API STD 520 | Sizing, Selection and Installation of Pressure Relieving Devices Part I and II | | |
| API STD 521 Pressure Relieving and Depressuring Systems | | | |
| API STD 681 | Liquid Ring Compressors and Vacuum Pumps in Petroleum, Chemical, and Gas Industry Services | | |
| ASME B16.5 | Pipe Flanges and Flanged Fittings | | |
| ASME B16.47 | Large Diameter Steel Flanges NPS 26 through NPS 60 Metric/Inch Standard | | |
| ASME B31.3 Process Piping | | | |
| ASME BPVC II Part A, B, C and D. Boiler and Pressure Vessel Code - Materia | | | |
| ASME BPVC V | Boiler and Pressure Vessel Code – Non-Destructive Examination | | |
| ASME BPVC VIII | Div.1 and Div. 2. Boiler and Pressure Vessel Code - Rules for Construction of Pressure Vessels | | |
| ASME BPVC IX | Qualification Standard for welding, brazing, and fusing procedures; Welders; Brazers; and Welding, Brazing and Fusing Operators | | |
| AWS D1.1 | Structural Welding Code – Steel | | |
| DOT-3A | Specification for Seamless Steel Transportable Pressure Receptacles | | |
| DOT-3AA | Specification for Seamless Steel Transportable Pressure Receptacles | | |
| IEC 60079 (all parts) | Explosive Atmospheres | | |
| IEC 61892 (all parts) Mobile and fixed offshore units – Electrical installations | | | |



| TECHNICAL SPECIFICATION No. I-ET-3010.2Q-1251-560-P | 4X-003 | REV: A |
|---|--------|--------|
| MARLIM LESTE E SUL | | |
| VACUUM DEAERATION UNIT (UT-1251003) | | SUP |
| VACOUM DEAERATION UNIT (UT-1251003) | INTE | RNAL |

| IEC 61672 (all parts) | Electroacoustics-Sound Level Meters |
|-----------------------|---|
| ISO 9809 (all parts) | Gas cylinders — Design, construction and testing of refillable seamless steel gas cylinders and tubes |
| ISO 13702 | Control and mitigation of fires and explosions on offshore production installations |
| ISO 15156 (all parts) | Materials for Use in H₂S-Containing Environments in Oil and Gas Production |
| ISO 21457 | Materials selection and corrosion control for oil and gas production systems |
| ISA 75.07 | Control Valve Noise Measurement and Prediction |

2.3 GOVERNMENT REGULATION

2.3.1 Brazilian Government regulations are mandatory and shall prevail, if more stringent, over the requirements of this specification and other references herein.

Table 2: Brazilian Regulatory Standard and Government Regulation

| NR-10 | - Brazilian Regulatory Standard - Safety in Electrical Facilities and Services |
|---------|--|
| NR-12 | - Brazilian Regulatory Standard – Safety in the Work of Machinery and Equipment |
| NR-13 | - Brazilian Regulatory Standard - Boilers, Pressure Vessels, Pipes and Metallic Storage Tanks |
| NR-17 | - Brazilian Regulatory Standard - Ergonomics |
| NR-26 | - Brazilian Regulatory Standard - Safety Signaling |
| NR-37 | - Brazilian Regulatory Standard - Safety and Health in Petroleum Platforms |
| IBAMA | - Brazilian IBAMA environmental regulations concerning the discharge of all types of effluents |
| INMETRO | - INMETRO Resolution no 115, March 21st 2022 |



| TECHNICAL SPECIFICATION No. I-ET-3010.2Q-1 | 251-560-P4X-003 REV: A | |
|--|------------------------|--|
| MARLIM LESTE E SUL | SHEET: 6 of 24 | |
| TITLE: E | | |
| VACUUM DEAERATION UNIT (UT-125 | INTERNAL | |

2.4 DESIGN SPECIFICATIONS

Table 3: Design Specifications

| | 5 . |
|---------------------------------|---|
| DR-ENGP-I-1.15 | - COLOR CODING |
| DR-ENGP-M-I-1.3 | - SAFETY ENGINEERING GUIDELINE |
| I-DE-3010.00-1400-140-P4X-004 | - GENERAL NOTES FOR TOPSIDES STRUCTURES |
| I-DE-3010.00-5140-797-P4X-002 | - ELECTRICAL SYSTEM AUTOMATION TYPICAL ACTUATION DIAGRAMS |
| I-DE-3010.00-5140-700-P4X-003 | - GROUNDING INSTALLATION TYPICAL DETAILS |
| I-DE-3010.2Q-1200-942-P4X-002 | - GENERAL ARRANGEMENT |
| I-DE-3010.2Q-1200-94A-P4X-001 | - AREA CLASSIFICATION – GENERAL |
| I-DE-3010.2Q-1251-944-P4X-005 | - VACUUM DEAERATION UNIT |
| I-DE-3010.2Q-1422-942-P4X-001 | - M-11 – INJECTION WATER AND SULPHATE REMOVAL – EQUIPMENT LAYOUT PLAN |
| I-DE-3010.2Q-5111-943-P4X-001 | - UTILITY FLOW DIAGRAM SEA WATER SYSTEM |
| I-ET-3000.00-1000-941-PPC-001_F | - METOCEAN DATA |
| I-ET-3000.00-1350-94P-P4X-002 | - DIGITAL ENGINEERING TECHNICAL REQUIREMENTS FOR DETAILED DESIGN |
| I-ET-3000.00-1200-940-P4X-001 | - TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN |
| I-ET-3000.00-5400-98G-P4X-001 | – EXPLOSION STUDY |
| I-ET-3010.00-1200-200-P4X-003 | - DESIGN, CONSTRUCTION AND ASSEMBLY OF FRP PIPING |
| I-ET-3010.00-1200-200-P4X-115 | - REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING |
| I-ET-3010.00-1200-200-P4X-116 | - REQUIREMENTS FOR BOLTED JOINTS ASSEMBLY AND MANAGEMENT |
| I-ET-3010.00-1200-251-P4X-001 | - REQUIREMENTS FOR BOLTING MATERIALS |
| I-ET-3010.00-1200-300-P4X-001 | - NOISE AND VIBRATION CONTROL REQUIREMENTS |
| I-ET-3010.00-1200-310-P4X-001 | - API 610 CENTRIFUGAL PUMPS SPECIFICATION |
| I-ET-3010.00-1200-310-P4X-002 | - POSITIVE DISPLACEMENT PUMPS SPECIFICATION |
| I-ET-3010.00-1200-310-P4X-003 | - NON-API 610 CENTRIFUGAL PUMPS SPECIFICATION |
| I-ET-3010.00-1200-431-P4X-001 | - THERMAL INSULATION FOR MARITIME INSTALLATIONS |
| I-ET-3010.00-1200-500-P4X-001 | - NON-METALLIC TANKS AND PRESSURE VESSELS DESIGN |
| I-ET-3010.00-1200-510-P4X-001 | - METALLIC TANKS DESIGN FOR TOPSIDE |
| I-ET-3010.00-1200-540-P4X-001 | - REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION |
| | |



| TECHN | NICAL SPECIFICATION No. I-ET-3010.2Q-1251-560 | - P4X-003 REV: A |
|-------------------------------------|---|-------------------------|
| | MARLIM LESTE E SUL | SHEET: 7 of 24 |
| TITLE: | | |
| VACUUM DEAERATION UNIT (UT-1251003) | | |

| I-ET-3010.00-1200-751-P4X-001 | - ANODES SPECIFICATION FOR MECHANICAL EQUIPMENT |
|-------------------------------|--|
| I-ET-3010.00-1200-800-P4X-002 | - AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS |
| I-ET-3010.00-1200-940-P4X-002 | - GENERAL TECHNICAL TERMS |
| I-ET-3010.00-1200-940-P4X-005 | - CHEMICAL INJECTION POINTS |
| I-ET-3010.00-1200-955-P4X-001 | - WELDING |
| I-ET-3010.00-1200-956-P4X-002 | - GENERAL PAINTING |
| I-ET-3010.00-1200-970-P4X-003 | - REQUIREMENTS FOR PERSONNEL QUALIFICATION AND CERTIFICATION |
| I-ET-3010.00-1200-970-P4X-004 | - NON-DESTRUCTIVE TESTING REQUIREMENTS FOR METALLIC AND NON-METALLIC MATERIALS |
| I-ET-3010.00-1200-970-P4X-013 | - COMPLIANCE WITH NR-13 AND SPIE REQUIREMENTS |
| I-ET-3010.00-1200-972-P4X-006 | - REQUIREMENTS FOR MANUFACTURING SURVEY INSPECTION |
| I-ET-3010.00-1200-978-P4X-005 | - REQUIREMENTS FOR MATERIALS TRACEABILITY |
| I-ET-3010.00-5140-700-P4X-001 | - SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-700-P4X-002 | - SPECIFICATION FOR ELECTRICAL MATERIAL FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-700-P4X-003 | - ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-700-P4X-007 | - SPECIFICATION FOR GENERIC ELECTRICAL EQUIPMENT FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-700-P4X-009 | - GENERAL REQUIREMENTS FOR ELECTRICAL MATERIAL AND EQUIPMENT FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-712-P4X-001 | - LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-712-P4X-002 | - MEDIUM-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-741-P4X-004 | - SPECIFICATION FOR LOW-VOLTAGE GENERIC ELECTRICAL PANELS FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-772-P4X-001 | - MEDIUM-VOLTAGE FREQUENCY CONVERTER FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-772-P4X-002 | - SPECIFICATION FOR LOW-VOLTAGE FREQUENCY CONVERTERS, SOFT-STARTERS AND INVERTERS FOR OFFSHORE UNITS |
| I-ET-3010.00-5140-797-P4X-001 | - ELECTRICAL SYSTEM AUTOMATION ARCHITECTURE |
| I-ET-3010.00-5400-947-P4X-002 | - SAFETY SIGNALLING |
| I-ET-3010.00-5518-767-PPT-002 | - TOPSIDES PUBLIC ADDRESS SYSTEM |
| | - AUTOMATION PANELS |



| | TECHNICAL SPECIFICATION No. I-ET-3010.2Q-1251-560-P4 | 4X-003 REV: A |
|---|--|----------------------|
| | MARLIM LESTE E SUL | SHEET: 8 of 24 |
| 8 | TITLE: VACUUM DEAEDATION UNIT (UT 1251002) | ESUP |
| | VACUUM DEAERATION UNIT (UT-1251003) | INTERNAL |

| I-ET-3010.2Q-1200-200-P4X-001 | - PIPING SPECIFICATION FOR TOPSIDES |
|-------------------------------|---|
| I-ET-3010.2Q-1200-200-P4X-004 | - REQUIREMENTS FOR PIPING SUPPORT |
| I-ET-3010.2Q-1200-200-P4X-005 | - REQUIREMENTS FOR PIPING MECHANICAL DESIGN AND LAYOUT |
| I-ET-3010.2Q-1200-200-P4X-006 | - REQUIREMENTS FOR PIPING FLEXIBILITY AND STRESS ANALYSIS |
| I-ET-3010.2Q-1200-500-P4X-001 | - MATERIAL SPECIFICATION FOR TOPSIDE SYSTEMS PRESSURE VESSELS AND TANKS |
| I-ET-3010.2Q-1200-800-P4X-014 | - AUTOMATION INTERFACE OF PACKAGED UNITS |
| I-ET-3010.2Q-1200-940-P4X-001 | - MATERIAL SELECTION PHILOSOPHY FOR DETAILED DESIGN |
| I-ET-3010.2Q-1400-140-P4X-001 | - TOPSIDES STRUCTURAL REQUIREMENTS |
| I-ET-3010.2Q-1400-196-P4X-001 | - ERGONOMICS REQUIREMENTS FOR TOPSIDES |
| I-FD-3010.2Q-1251-560-P4X-003 | - VACUUM DEAERATION UNIT (UT-1251003) |
| I-FD-3010.2Q-1251-565-P4X-001 | - VACUUM DEAERATION COLUMN (D-UT-1251003) |
| I-FD-3010.2Q-5400-947-P4X-001 | - SAFETY DATA SHEET - TOPSIDES |
| I-LI-3010.00-5140-797-P4X-001 | - ELECTRICAL SYSTEM AUTOMATION INTERFACE SIGNALS LIST |
| I-MD-3010.00-5510-760-PPT-001 | - GENERAL CRITERIA FOR TELECOMMUNICATIONS DESIGN |
| I-MD-3010.2Q-1200-947-P4X-003 | - DESCRIPTIVE MEMORANDUM – SAFETY |
| I-MD-3010.2Q-1200-970-P4X-001 | - COMISSIONING DESCRIPTIVE MEMORANDUM |
| I-RL-3010.2Q-1200-940-P4X-001 | - GENERAL SPECIFICATION FOR AVAILABLE UTILITIES |
| I-RL-3010.2Q-1350-960-P4X-002 | - MOTION ANALYSIS |

2.5 CONFLICTING REQUIREMENTS

2.5.1 In case of conflicting requirements between this technical specification and other cited references, the most stringent shall prevail. If necessary, the SELLER may revert to BUYER for clarification.

3 DEFINITIONS AND ABBREVIATIONS

3.1 **DEFINITIONS**

3.1.1 All Terms and definitions are established in the latest revision I-ET-3010.00-1200-940-P4X-002 - GENERAL TECHNICAL TERMS.

3.2 ABBREVIATIONS

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|----------------------|
| BR | MARLIM | LESTE E SUL | SHEET: 9 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

AEPR - Automation & Electrical Panel Room

CLASS - Classification Society

FAT - Factory Acceptance Test

FPSO - Floating Production Storage and Offloading

GRP - Glass- Reinforced Plastic

HAZOP - Hazard and Operability Study

ITP - Inspection and Test Plans

NPS - Nominal Pipe Size

NDT - Non-Destructive Test

PHA - Process Hazards Analysis

PAGA - Public Address and General Alarm

PP - Polypropylene SS - Stainless steel

4 PACKAGE REQUIREMENTS

4.1 SCOPE OF SUPPLY

- 4.1.1 The SELLER shall select a sub supplier considering a proven experience supplying this type of equipment/technology. SELLER shall submit the name of the sub supplier to BUYER approval.
- 4.1.2 The Vacuum Deaeration Unit (UT-1251003) shall be complete in all respect and the scope of supply shall include but not be limited to the major equipment described in the document I-FD-3010.2Q-1251-560-P4X-003 VACUUM DEAERATION UNIT (UT-1251003) and I-DE-3010.2Q-1251-944-P4X-005 VACUUM DEAERATION UNIT.
- 4.1.3 The scope of supply of the Vacuum Deaeration Unit (UT-1251003) shall also include the following major systems: D-UT-1251003 Vacuum Deaerator Column and the Z-UT-1251003 Vacuum System both described in I-FD-3010.2Q-1251-560-P4X-003 VACUUM DEAERATION UNIT (UT-1251003) and I-FD-3010.2Q-1251-565-P4X-001 VACUUM DEAERATION COLUMN (D-UT-1251003)

4.2 PROCESS DESIGN

- 4.2.1 SELLER shall design and size the equipment of package for the full range of process conditions as specified in:
 - I-FD-3010.2Q-1251-560-P4X-003
 VACUUM DEAERATION UNIT (UT-1251003).
 - I-DE-3010.2Q-1251-944-P4X-005
 VACUUM DEAERATION UNIT.
 - I-FD-3010.2Q-1251-565-P4X-001 VACUUM DEAERATION COLUMN (D-UT- 1251003)
- 4.2.2 Design shall also include the definition of number, size and location of all process and instrument related nozzles in the battery limits of the package (refer to the I-DE-3010.2Q-1251-944-P4X-005 VACUUM DEAERATION UNIT).

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P4 | 4X-003 REV: A |
|-----------|-------------------------|------------------------------|-----------------|
| BR | MARLIM | LESTE E SUL | SHEET: 10 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | 10N 0N11 (01-1251003) | INTERNAL |

4.3 OPERATION ENVIRONMENT

4.3.1 The equipment supplied shall be suitable for the environment and range of ambient condition defined in the revision F of I-ET-3000.00-1000-941-PPC-001_F - METOCEAN DATA

4.4 MOTION REQUIREMENTS

4.4.1 The necessary design data and information on motion requirements are given in I-RL-3010.2Q-1350-960-P4X-002 - MOTION ANALYSIS.

4.5 PACKAGE LOCATION AND AREA CLASSIFICATION

- 4.5.1 The Vacuum Deaeration Unit (UT-1251003) shall be installed on module M-11 as informed in I-DE-3010.2Q-1200-942-P4X-002 GENERAL ARRANGEMENT. For available space, also see I-DE-3010.2Q-1422-942-P4X-001 M-11 INJECTION WATER AND SULPHATE REMOVAL EQUIPMENT LAYOUT PLAN.
- 4.5.2 For area classification see I-DE-3010.2Q-1200-94A-P4X-001 AREA CLASSIFICATION GENERAL.

4.6 DESIGN LOADS

- 4.6.1 In addition to the Code described loads and loads due to vessel motion described in I-RL-3010.2Q-1350-960-P4X-002 MOTION ANALYSIS, the following design loads shall be considered whenever applicable:
 - Equipment transportation and erection loads.
 - Nozzle loads.
 - Thermal loads.
 - Wind loads in METOCEAN DATA.
 - Weight loads.
 - Blast loads (according to I-ET-3000.00-5400-98G-P4X-001 EXPLOSION STUDY)
 - Fatigue loads.

4.7 DESIGN LIFETIME

4.7.1 The SELLER shall design and manufacture the complete equipment of the package for a minimum useful life of 25 years.

4.8 NOISE AND VIBRATION

4.8.1 Noise and vibration control concerning human exposure shall be performed according to I-ET-3010.00-1200-300-P4X-001 - NOISE AND VIBRATION CONTROL REQUIREMENTS.

4.9 ELECTRONIC MODEL

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|----------------------|
| BR | MARLIM | LESTE E SUL | SHEET: 11 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

- 4.9.1 VENDOR shall develop full 3D model according to the requirements stated in I-ET-3000.00-1350-94P-P4X-002 - DIGITAL ENGINEERING TECHNICAL REQUIREMENTS FOR DETAILED DESIGN
- 4.9.2 3D model shall include valve categorization according to I-ET-3010.2Q-1400-196-P4X-001
 ERGONOMICS REQUIREMENTS FOR TOPSIDES. Manually operated valves shall have type of handle, direction and height from floor as 3D model attributes.

4.10 PIPING

- 4.10.1 Piping shall have valves (on/off valves) and/or flanges and blind flanges (ASME B16.5/B16.47) at the end of unit limits.
- 4.10.2 Piping specification (specs) and valves shall follow the technical specification I-ET-3010.2Q-1200-200-P4X-001 PIPING SPECIFICATION FOR TOPSIDES. Alternative piping specifications and valves shall be submitted to BUYER for approval.
- 4.10.3 Piping layout shall observe the requirements presented on I-ET-3010.2Q-1200-200-P4X-005 REQUIREMENTS FOR PIPING MECHANICAL DESIGN AND LAYOUT.
- 4.10.4 Piping stress analysis shall be performed according to I-ET-3010.2Q-1200-200-P4X-006 REQUIREMENTS FOR PIPING FLEXIBILITY AND STRESS ANALYSIS.
- 4.10.5 Piping shall be properly supported considering the service loads, shipment, results of pipe flexibility analysis studies and transportation loads. Piping supports shall be in accordance with I-ET-3010.2Q-1200-200-P4X-004 REQUIREMENTS FOR PIPING SUPPORT. Supports applied directly to the module base plates shall not be performed without prior under deck stiffening. The supporting and installation shall enable piping removal without disturbing structural members.
- 4.10.6 Socket welding connections are only permitted for piping sizes equal or less than 1½ inch NPS (Nominal Pipe Size). All piping above 1½ inch shall be butt-welded.
- 4.10.7 The use of concentric type butterfly valves and straight-through diaphragm valves with open body (open body tubular diaphragm valves) is not permitted.
- 4.10.8 The use of elastomeric throttle valves exposed to UV radiation is not allowed.
- 4.10.9 Sampling point / facilities shall be provided complete with necessary fittings and valves, and the design should reflect nature of the fluids being sampled.
- 4.10.10 Utility hose stations shall be installed throughout the package on strategic places for maintenance and cleaning purposes.
- 4.10.11 The design, assembly and commissioning of all process piping shall be according to
 - ASME B31.3 PROCESS PIPING.
 - I-ET-3010.00-1200-200-P4X-115 REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING.
 - I-ET-3010.2Q-1200-200-P4X-005 REQUIREMENTS FOR PIPING MECHANICAL DESIGN AND LAYOUT.
- 4.10.12 FRP piping shall follow the requirements stated in I-ET-3010.00-1200-200-P4X-003 DESIGN, CONSTRUCTION AND ASSEMBLY OF FRP PIPING.
- 4.10.13 All structural supports including main structural skid, support frames, supports for equipment, ladders, walkways, platforms, grating and drip trays shall be provided.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|-----------------|
| BR | MARLIM | LESTE E SUL | SHEET: 12 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUN DEAERAT | ION ONIT (01-1251003) | INTERNAL |

- 4.10.14 All other miscellaneous items and equipment which are required for the service and proper operation of the Unit shall be included.
- 4.10.15 SELLER shall provide a design book with all piping detailed design documentation, which must include, but not be limited, to the following documents: isometrics, piping plan, support detail drawings, stress analysis report (with native program file), list of supports, valve list, special item list, document list, stress analysis list, tie-in list, welding procedures, strainers datasheet, and piping elements datasheet.

4.11 THERMAL INSULATION

4.11.1 The thermal insulation shall be according to latest revision of I-ET-3010.00-1200-431-P4X-001 - THERMAL INSULATION FOR MARITIME INSTALLATIONS.

4.12 BOLTS AND NUTS

- 4.12.1 All fasteners (stud bolts, tightening bolts and nuts) shall be according to I-ET-3010.00-1200-251-P4X-001- REQUIREMENTS FOR BOLTING MATERIALS.
- 4.12.2 Bolted joints within the package shall be assembled and managed as stablished in I-ET-3010.00-1200-200-P4X-116- REQUIREMENTS FOR BOLTED JOINTS ASSEMBLY AND MANAGEMENT.

4.13 PAINTING

- 4.13.1 Painting requirements shall be according to I-ET-3010.00-1200-956-P4X-002 GENERAL PAINTING.
- 4.13.2 Color code adopted shall be in accordance with DR-ENGP-I-1.15 COLOR CODING.

4.14 STRUCTURES

- 4.14.1 The structure and their foundations shall be designed according to CLASS rules and all requirements and conditions indicated in I-ET-3010.2Q-1400-140-P4X-001 TOPSIDES STRUCTURAL REQUIREMENTS
- 4.14.2 All materials used for SKID/PACKAGE structure shall met the CLASS rules and specifications indicated in I-DE-3010.00-1400-140-P4X-004 GENERAL NOTES FOR TOPSIDES STRUCTURES.
- 4.14.3 The SELLER is responsible for the materials selection considering the philosophy detailed at I-ET-3010.2Q-1200-940-P4X-001 MATERIAL SELECTION PHILOSOPHY FOR DETAILED DESIGN, and the operational condition and process data stated at I-FD-3010.2Q-1251-560-P4X-003 VACUUM DEAERATION UNIT (UT-1251003).

4.15 MATERIAL SELECTION AND CERTIFICATION

4.15.1 Materials of construction for the Vacuum Deaerator Column (D-UT-1251003) shall be in accordance with I-ET-3010.2Q-1200-500-P4X-001 - MATERIAL SPECIFICATION FOR TOPSIDE SYSTEMS PRESSURE VESSELS AND TANKS.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P4 | 4X-003 REV: A |
|-----------|-------------------------|------------------------------|-----------------|
| BR | MARLIM | LESTE E SUL | SHEET: 13 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUN DEAERAT | 10N 0N11 (01-1251003) | INTERNAL |

- 4.15.2 The materials of construction for the liquid ring pumps and the ejectors shall be 25% Cr duplex.
- 4.15.3 Separator tank shall be made of GRP.
- 4.15.4 SELLER may offer materials of construction other than those specified, but these shall be quoted separately as an alternative.
- 4.15.5 In all cases, SELLER shall submit the detailed material selection report, including all piping, equipment, and their components, for BUYER approval prior to manufacturing activities.
- 4.15.6 SELLER shall be responsible for obtaining all necessary certification of the equipment, work, and materials.
- 4.15.7 SELLER through the independent certifying authority shall supply all certificates related to the materials, inspections, tests, and qualification activities detailed in the approved Quality Plan.

4.16 PUMPS

- 4.16.1 Vacuum pumps (B-Z-UT-1251003 A/B):
 - The vacuum pumps shall be liquid ring type and supplied in accordance with API STD 681
 - It shall be provided with spacer couplings, including non-sparking coupling guards.
 - It shall be supplied with: flowmeter for each pump, level transmitter, water sealing temperature measurement, bearing vibration sensor.
- 4.16.2 Others pumps shall comply with the requirements of:
 - I-ET-3010.00-1200-310-P4X-001 API 610 CENTRIFUGAL PUMPS SPECIFICATION.
 - I-ET-3010.00-1200-310-P4X-002 POSITIVE DISPLACEMENT PUMPS SPECIFICATION; or
 - I-ET-3010.00-1200-310-P4X-003
 NON-API 610 CENTRIFUGAL PUMPS SPECIFICATION.
- 4.16.3 For pumps up to 7.5 kW, working with non-flammable and non-hazardous service, vendor may use its own specification, i.e., no specific design code will be applicable, provided that field proven requirements for the PACKAGE are fulfilled and if approved by BUYER previously during the package technical proposal. Material selection shall still be performed as per ISO 21457.
- 4.16.4 Electrical equipment, installations and voltages shall always comply with item 4.26.

4.17 PRESSURE VESSELS

- 4.17.1 All pressure vessels, columns and filters shall comply with:
 - The requirements of last revision of Brazilian Regulatory Standard NR-13.
 - I-ET-3010.00-1200-970-P4X-013 COMPLIANCE WITH NR-13 AND SPIE REQUIREMENTS; and
 - I-ET-3010.00-1200-540-P4X-001 REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|----------------------|
| BR | MARLIM | LESTE E SUL | SHEET: 14 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

 If the scope of supply includes any transportable pressure vessels, connected with process plant or platform installations, these items shall be within the scope of NR-13 regulation. Furthermore, transportable containers shall be designed, constructed, inspected and installed in accordance with the requirements addressed by a specific rule of transportable equipment, such as ISO 9809, DOT-3A or DOT-3AA.

4.18 NON-METALLIC TANK AND PRESSURE VESSEL

4.18.1 Non-metallic tanks and non-metallic pressure vessels shall comply with the requirements of I-ET-3010.00-1200-500-P4X-001- NON-METALLIC TANKS AND PRESSURE VESSELS DESIGN.

4.19 METALLIC TANK

- 4.19.1 Metallic tanks shall comply with the requirements of I-ET-3010.00-1200-510-P4X-001 METALLIC TANKS DESIGN FOR TOPSIDE.
- 4.19.2 Discharge separator tank stiffeners shall be internal where necessary.

4.20 WELDING AND WELDING INSPECTION

- 4.20.1 All equipment (such as pressure vessels, filters, tanks, heat exchangers, pump, turbomachinery etc.), structures, valves and piping weldments shall be according to the requirements stated in I-ET-3010.00-1200-955-P4X-001 WELDING.
- 4.20.2 Welding shall be carried out with procedures and welders qualified in accordance with Design Code and additional requirements stated in contractual technical specifications. Welding shall not be performed before qualified welding procedures specification have been approved.
- 4.20.3 Intermittent fillet welds are not permitted.
- 4.20.4 Welding inspection shall be according to the Design Code and additional requirements stated in the contractual technical specification, such as:
 - I-ET-3010.00-1200-200-P4X-115 REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING.
 - I-ET-3010.00-1200-540-P4X-001 REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION.
 - I-DE-3010.00-1400-140-P4X-004 GENERAL NOTES FOR TOPSIDES STRUCTURES, etc.
- 4.20.5 Welding repairs and heat treatments must be recorded and submitted for BUYER's approval.

4.21 NON DESTRUCTIVE TESTING - NDT

- 4.21.1 NDT shall be according to the Design Code and I-ET-3010.00-1200-970-P4X-004 NON-DESTRUCTIVE TESTING REQUIREMENTS FOR METALLIC AND NON-METALLIC MATERIALS.
- 4.21.2 Final NDTs, for acceptance purposes shall be performed after completion of any post weld heat treatment (when applicable) and prior to paint application, hydrostatic testing, etc.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|-----------------|
| BR | MARLIM | LESTE E SUL | SHEET: 15 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

4.22 ERGONOMICS REQUIREMENTS

- 4.22.1 The package shall be arranged such to allow safe and good personnel access for all operation and maintenance activities and in accordance with I-ET-3010.2Q-1400-196-P4X-001 ERGONOMICS REQUIREMENTS FOR TOPSIDES.
- 4.22.2 SELLER shall prepare detailed assembly, disassembly, and maintenance procedures, describing the use of all involved handling devices and including all required preventive and corrective maintenance tasks. SELLER shall inform the need for disassembling any component or equipment to facilitate access for maintenance. Suitable maintenance routes shall be provided to remove the main components and auxiliaries, avoiding interference with structures, piping, cabling, electric conduits and supports, equipment etc. This plan shall be submitted to BUYER for approval.
- 4.22.3 All valves shall be positioned with the stem pointing upwards. They shall be located in such a way that the hand wheel or actuator will not obstruct escape routes, walkways and be easily accessible for operation and maintenance, according to I-ET-3010.2Q-1400-196-P4X-001 ERGONOMICS REQUIREMENTS FOR TOPSIDES. Where hand operated valves are not easily operable, gear operated valves shall be used.
- 4.22.4 Ladders and platform shall be provided to access operational devices, e.g., valves, instruments, manways, etc., whether located in an elevation greater than 1.75 m over the module base plate.
- 4.22.5 The level gauges shall be installed in such position that the level indicated in receiver will be easily seen. All level gauges shall have flanged connections, which can be isolated, and be complete with vent and drain, valves and connection, to facilitate the maintenance tasks.

4.23 SAFETY REQUIREMENTS

- 4.23.1 Pressure relief system and devices shall comply with the requirements of API STD 521.
- 4.23.2 For area classification see I-DE-3010.2Q-1200-94A-P4X-001 AREA CLASSIFICATION GENERAL.
- 4.23.3 Mandatory safety items, as established in DR-ENGP-M-I-1.3 SAFETY ENGINEERING GUIDELINE, are to be considered complementary requirements, to the pertinent extent. In case of items in conflict with this document, BUYER shall be consulted.
- 4.23.4 Safety design additional requirements see I-MD-3010.2Q-1200-947-P4X-003 DESCRIPTIVE MEMORANDUM SAFETY, and I-FD-3010.2Q-5400-947-P4X-001 SAFETY DATA SHEET TOPSIDE.
- 4.23.5 HAZOP and PHA shall be performed according to DR-ENGP-M-I-1.3 SAFETY ENGINEERING GUIDELINE.
- 4.23.6 Double block & bleed arrangements are required for isolation of equipment in piping class 300# and above.
- 4.23.7 All safety signs and notices shall be in Portuguese language according to I-ET-3010.00-5400-947-P4X-002 SAFETY SIGNALLING.

4.24 INSTRUMENTATION

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------------------|-------------------------|-----------------------------|----------------------|
| BR MARLIM LESTE E SUL | | LESTE E SUL | SHEET: 16 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

- 4.24.1 All instrumentation equipment and interface with FPSO automation and control design shall comply with I-ET-3010.00-1200-800-P4X-002 AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS.
- 4.24.2 For package automation type classification and additional interfaces see I-ET-3010.2Q-1200-800-P4X-014 AUTOMATION INTERFACE OF PACKAGED UNITS.
- 4.24.3 All control, monitoring and safety protection instruments, instrumented valves, devices, and associated accessories (such as, but not limited to, tubings, thermowells, etc) for remote indication, control, alarms, protection and shut down, etc. shall be included.
- 4.24.4 Automatic temperature control facilities shall be provided for the control of cooling medium flow.
- 4.24.5 Package Unit Control Panel shall fully comply with requirements of I-ET-3010.00-5520-888-P4X-001 AUTOMATION PANELS.

4.25 UNIT CONTROL PANEL

- 4.25.1 Unit Control Panel (PN-Z-UT-1251003) supplied loose to be installed on FPSO module.
- 4.25.2 Unit Control Panel (PN-Z-UT-1251003) shall be installed in the Topside AEPR, which is a non-hazardous area.
- 4.25.3 The panel shall be capable of carrying out interlocking, process automation and start-up, shutdown, normal operation and safety procedures.

4.26 ELECTRICAL

- 4.26.1 All materials and equipment proper to be used in hazardous areas shall have conformity certificates complying with the latest revision of IEC-60079 and all its parts; PORTARIA INMETRO Nº 115 (March 21st, 2022); and shall be approved by Classification Society.
- 4.26.2 Electrical equipment installed in external safe areas, which shall be kept operating during emergency shutdown ESD-3P and ESD-3T shall be certified for installation in hazardous areas Zone 2 (EPL Gc) Group IIA temperature T3, unless they are automatically disconnected in case of confirmed gas in the equipment area, according to IEC 61892-1.
- 4.26.3 Low-voltage and Medium-voltage motors inside the package shall comply with latest revision of I-ET-3010.00-5140-712-P4X-001 LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS and I-ET-3010.00-5140-712-P4X-002 MEDIUM-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS.
- 4.26.4 All electrical equipment and material shall fully comply with:
 - I-ET-3010.00-5140-700-P4X-002 SPECIFICATION FOR ELECTRICAL MATERIAL FOR OFFSHORE UNITS.
 - I-ET-3010.00-5140-700-P4X-007 SPECIFICATION FOR GENERIC ELECTRICAL EQUIPMENT FOR OFFSHORE UNITS
 - I-ET-3010.00-5140-700-P4X-009 GENERAL REQUIREMENTS FOR ELECTRICAL MATERIAL AND EQUIPMENT FOR OFFSHORE UNITS;
 - I-ET-3010.00-5140-741-P4X-004 SPECIFICATION FOR LOW-VOLTAGE GENERIC ELECTRICAL PANELS FOR OFFSHORE UNITS.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|----------------------|
| BR | MARLIM | LESTE E SUL | SHEET: 17 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

- I-ET-3010.00-5140-772-P4X-001 MEDIUM-VOLTAGE FREQUENCY CONVERTER FOR OFFSHORE UNITS
- I-ET-3010.00-5140-772-P4X-002 SPECIFICATION FOR LOW-VOLTAGE FREQUENCY CONVERTERS, SOFT-STARTERS AND INVERTERS FOR OFFSHORE UNITS
- 4.26.5 Power lighting and grounding installations inside the package shall comply with requirements of I-ET-3010.00-5140-700-P4X-001 SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS, I-ET-3010.00-5140-700-P4X-003 ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS and, I-DE-3010.00-5140-700-P4X-003 GROUNDING INSTALLATION TYPICAL DETAILS.
- 4.26.6 Interfaces of the Package with Electrical System shall comply with I-ET-3010.00-5140-797-P4X-001 ELECTRICAL SYSTEM AUTOMATION ARCHITECTURE, I-DE-3010.00-5140-797-P4X-002 ELECTRICAL SYSTEM AUTOMATION TYPICAL ACTUATION DIAGRAMS and I-LI-3010.00-5140-797-P4X-001 ELECTRICAL SYSTEM AUTOMATION INTERFACE SIGNALS LIST

4.27 TELECOMMUNICATIONS REQUIREMENTS

- 4.27.1 Design of PAGA equipment shall fulfill the requirements, including standards and documents referred herein as well as referenced on project data sheets and system technical specification. PAGA installations and interfaces shall comply with requirements of:
 - a. I-ET-3010.00-5518-767-PPT-002 TOPSIDES PUBLIC ADDRESS SYSTEM.
 - b. I-MD-3010.00-5510-760-PPT-001 GENERAL CRITERIA FOR TELECOMMUNICATIONS DESIGN.
 - c. I-ET-3010.2Q-1400-196-P4X-001 ERGONOMICS REQUIREMENTS FOR TOPSIDES
- 4.27.2 Package shall be delivered with PAGA horns and cables installed and tested based on detail design done by SELLER.
- 4.27.3 SELLER shall be responsible for the design, supplying, installation and integration of the Public Address and General Alarm System (PAGA) items of its package, complying with all applicable requirements described in I-ET-3010.00-5518-767-PPT-002 TOPSIDES PUBLIC ADDRESS SYSTEM for the entire system.
- 4.27.4 Since the PAGA network inside package to be designed by SELLER is part of the entire system that is scope of SELLER detail design, SELLER shall ask BUYER any specific characteristics of the system, as well as the approval of the sound calculation memories and detailed design, to assure fully interoperability.
- 4.27.5 The acoustic horns and cables shall be designed by SELLER in two different and independent groups A and B. Each of these groups shall be ended inside a proper interface box to be installed at the edge of the package, in accordance with the classifications zone and groups established by IEC / ABNT and FPSO EPCI Integrator.
- 4.27.6 SELLER shall be responsible for commissioning the PAGA network inside package of its own scope of supply before the lifting of the package, when BUYER will accept the system.
- 4.27.7 SELLER shall supply all needed facilities to test the PAGA network inside package before lifting.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------|-----------------------------|-----------------|
| BR | MARLIM | LESTE E SUL | SHEET: 18 of 24 |
| PETROBRAS | TITLE: VACUUM DEAEDAT | ION UNIT (UT-1251003) | ESUP |
| | VACOUW DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

- 4.27.8 Wherever there are closed areas in package module, they shall also be covered by UHF, LTE and WLAN systems. So, SELLER shall make available MCT (Multi cable and pipe transit) for cables entrance and internal fixing supports for internal UHF and LTE antennas and their RF cables and industrial access points with its fiber optic cable and electrical cable. Such equipment and cables will be delivered by SELLER according to its detail design, if required.
- 4.27.9 Since the UHF Active Repeater, LTE and WLAN Systems are part of complete systems that are in the scope of the SELLER, SELLER shall ask the BUYER any specific characteristics of infrastructure required and detailed design to assure interoperability and functionality inside closed areas of packages module.

4.28 INSTALLATION REQUIREMENTS

- 4.28.1 SKID DETAILS
- 4.28.1.1 This section is only applicable for equipment that is built on a skid.
- 4.28.1.2 The skid shall be designed to accommodate the entire equipment within the scope of supply. The skid shall be of rigid construction, which will not distort during hoisting, operation and shipment and shall withstand all moments and forces due to the vessel motion.
- 4.28.1.3 All equipment shall be installed by SELLER over structural steel deck plate in position shown in I-DE-3010.2Q-1422-942-P4X-001 M-11 INJECTION WATER AND SULPHATE REMOVAL EQUIPMENT LAYOUT PLAN.
- 4.28.1.4 All piping terminations shall be flanged.
- 4.28.1.5 The set of equipment and its skid shall be designed, arranged and assembled in such a way as to allow safe access for personnel for all operations and maintenance tasks (mechanical, electrical, painting, insulation, etc.).
- 4.28.1.6 Lifting facilities shall enable lifting of the equipment with crane as a single point lift for transportation and installation. The design and manufacture of the lifting lugs shall be certified. The arrangement of equipment, piping and superstructure shall be such that the center of gravity coincides approximately with the geometrical center of the skid when lifting the skids, complete with all equipment mounted, beam deflection shall not exceed 1/400 L.
- 4.28.1.7 The skid shall resist all sling forces, including both horizontal and vertical components of the applied sling angle (sling angles shall be within between 50 and 90° with the horizontal plane).
- 4.28.1.8 Lifting beams, spreader bars, slings, shackles, etc. are within SELLER's scope of supply.
- 4.28.1.9 Drip trays with drain connections shall be provided underneath equipment where significant spillage is likely to occur.
- 4.28.1.10 The skid shall be welded to the supporting structures. Skid floor shall be made of plate material with a raised on-slip tread. Welds underneath skid beams shall be ground flush. Skid shall have two diagonally opposed earthing bars.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------------------|-----------------------------|---------------|
| BR | MARLIM | SHEET: 19 of 24 | |
| PETROBRAS | VACUUM DEAERATION UNIT (UT-1251003) | | ESUP |
| | VACOUM DEAERAT | ATION UNIT (UT-1251003) | INTERNAL |

4.28.2 MAINTENANCE LIFTING BEAMS

- 4.28.2.1 All required maintenance lifting beams, complete with the necessary hoisting and lifting gear, shall be provided to facilitate safe and easy maintenance.
- 4.28.2.2 All lifting beams shall overhang by at least 1.2 m into agreed lay-down areas.
- 4.28.2.3 The deflection of the maintenance crane/hoisting beams shall not exceed 1/500 of the span length.
- 4.28.2.4 All beams and lifting gear shall be subject to load testing, witnessed by BUYER representative and CLASS.

4.29 NAMEPLATES

- 4.29.1 SELLER shall install in all package equipment nameplate made of stainless steel 316 in an accessible location, fastened with corrosion resistant stainless-steel type 316 pins, and in Portuguese language.
- 4.29.2 For pressure vessels, columns and filters the nameplates shall be according to I-ET-3010.00-1200-540-P4X-001- REQUIREMENTS FOR PRESSURE VESSELS DESIGN AND FABRICATION.
- 4.29.3 For other equipment, nameplates shall include following information as a minimum:
 - Petróleo Brasileiro S.A. PETROBRAS.
 - Purchase order number.
 - Manufacturer and year of build.
 - Tag number.
 - · Service.
 - · Serial number.
 - Main data for design, operation and testing (Power, Pressure, Volume, Temperature, Rotation, Flow rate), where applicable.
 - Specific requirements.
 - Installation identification.
 - Driver power rating and speed, where applicable.
 - Design code.
 - · Empty weight.
 - NR-13 information (if applicable).
- 4.29.4 Valves, instruments, and orifices shall be tagged with the applicable number only.

4.30 TAG NUMBERING

- 4.30.1 Tagging of all instruments, electrical, telecommunications, mechanical and piping items, including valves, shall be in accordance with latest revision of I-ET-3000.00-1200-940-P4X-001 TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN.
- 4.30.2 For main item tag numbers, refer to I-FD-3010.2Q-1251-560-P4X-003 VACUUM DEAERATION UNIT (UT-1251003).

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------------------|-----------------------------|----------------------|
| BR | MARLIM | SHEET: 20 of 24 | |
| PETROBRAS | VACUUM DEAERATION UNIT (UT-1251003) | | ESUP |
| | | | INTERNAL |

4.30.3 Tag numbers for remaining ancillary equipment shall be given after purchase order placement.

5 CERTIFICATION REQUIREMENTS

5.1 CLASSIFICATION SOCIETY CERTIFICATION

- 5.1.1 SELLER shall provide a CLASS Certificate of Compliance for the entire Unit.
- 5.1.2 In order to obtain the Certificate of Compliance all related CLASS activities and CLASS technical requirements are within the SELLER scope of work, as well as all cost associated with it.

5.2 HAZARDOUS AREAS CERTIFICATION

5.2.1 All materials and equipment proper to be used in hazardous areas, shall have conformity certificates complying with the latest revision of IEC-60079 and all its parts; PORTARIA INMETRO Nº 115 (March 21st, 2022); and shall be approved by Classification Society.

6 INSPECTION, TESTING AND COMMISSIONING

6.1 GENERAL

- 6.1.1 SELLER is required to propose a program for inspection and testing of all supplied equipment for approval by BUYER, prior to commencement of work in accordance with document schedule. Inspection and Test Plans (ITP) shall be issued for each equipment that are part of the Unit.
- 6.1.2 Unless otherwise stated, all inspections and tests shall be performed at the workshop of SELLER in the presence of BUYER representative and CLASS surveyor as applicable.
- 6.1.3 Inspections and tests are an integral part of the order which will not be considered complete until such inspections and tests have been carried out in full and recorded in an inspection report that shall be part of the data-book.
- 6.1.4 BUYER shall issue an Inspection Release Certificate (IRC) only after completion of all required inspections and tests and after the manufacturing data-books have been issued and approved.

6.2 PERSONNEL QUALIFICATION AND CERTIFICATION

6.2.1 Personnel qualification and certification shall be in accordance with I-ET-3010.00-1200-970-P4X-003- REQUIREMENTS FOR PERSONNEL QUALIFICATION AND CERTIFICATION.

6.3 QUALITY AND INSPECTION


6.3.1 SELLER shall provide documented schedules with the estimated completion dates. These schedules shall be issued by the same time the drawings are submitted for approval, as indicated in the agreed document schedule.

| | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A | |
|-----------|-------------------------------------|-----------------------------|----------------------|--|
| BR | MARLIM LESTE E SUL | | | |
| PETROBRAS | VACUUM DEAERATION UNIT (UT-1251003) | | ESUP | |
| | | | INTERNAL | |

- 6.3.2 BUYER reserves the right to inspect all items at any time during fabrication to ensure that the materials and workmanship are in accordance with this specification and all applicable documentation.
- 6.3.3 SELLER is responsible for the overall compliance of the Unit when it comes to the CLASS requirements, including certificates, work examinations and tests, as well as final inspection activities and shipment.
- 6.3.4 In addition to BUYER inspection, equipment such as valves and fittings, etc. shall be subject to all CLASS authority and may range from a review of SELLER's quality manual to a physical survey of SELLER's shop or end products.
- 6.3.5 The CLASS inspector shall have the right to request inspections or examinations to ensure that the equipment complies with the relevant CLASS requirements. If examination reveals any deficiencies, SELLER shall bear the full cost of repair or replacement when necessary. BUYER shall approve any repair work. The subsequent examination necessary to ensure the satisfactory manufacture of the equipment in question will be on behalf of the SELLER.
- 6.3.6 Except if approved by BUYER inspector, all equipment shall be presented for inspection in an unpainted state. SELLER shall provide notice to the inspector to witness the specified tests at least 2 (two) weeks in advance for Brazilian MANUFACTURER and 3 (three) weeks for foreign MANUFACTURER.
- 6.3.7 Manufacturing Survey Inspection shall be performed according to I-ET-3010.00-1200-972-P4X-006 - REQUIREMENTS FOR MANUFACTURING SURVEY INSPECTION.
- 6.3.8 Traceability of material shall comply with I-ET-3010.00-1200-978-P4X-005 REQUIREMENTS FOR MATERIALS TRACEABILITY.
- 6.3.9 Equipment, piping and accessories under scope of Brazilian Regulatory Standard NR-13 shall comply with I-ET-3010.00-1200-970-P4X-013 COMPLIANCE WITH NR-13 AND SPIE REQUIREMENTS.

6.4 TESTING

- 6.4.1 The following tests shall be included in SELLER's scope and shall be performed in the presence of BUYER inspectors:
 - a) Pressure test (usually hydrostatic) of all vessels, heat exchangers, tanks and piping/valves.
 - b) Electrical insulation and continuity checks on all wiring and earthing.
 - c) Insulation (MEGGER) test for cables and electric motors shall be provided.
 - d) Tests stated in the respective motors and power/control panel specifications.
 - e) Functional checks on all instruments and valves.
 - f) Pumps running tests
- 6.4.2 All piping systems and equipment shall be drained and dried after hydrostatic testing.
- 6.4.3 All pumps shall be tested as per relevant codes (API 674, API 675, API 676 or API 681).
- 6.4.4 Preservation to be applied shall follow the requirements of I-ET-3010.00-1200-200-P4X-115 - REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING.
- 6.4.5 Low-voltage and Medium-voltage motors shall be tested according to I-ET-3010.00-5140-712-P4X-001- LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS and I-ET-



3010.00-5140-712-P4X-002- MEDIUM-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS.

6.5 PACKAGE INSPECTION

- 6.5.1 BUYER Inspector shall witness the following inspections and checks:
 - Verification of equipment construction materials (vessels, heat exchangers, pumps, etc.) for conformity with the specification requirements.
 - Verification of piping, fittings and valves conform to specification of materials and fabrication.
 - Reports for all NDT performed on the pressure retaining parts (radiographic, dye penetrant, magnetic particles, and ultrasonic inspection).
 - Approval of the relief valve settings and witness of their testing after setting.
 - Review of Inspection and Test Records.
 - A visual check noting:
 - That the thickness of the pressure retaining parts meets or exceeds the quoted design thickness.
 - Any repairs.
 - Dry-film thickness of applied coatings.
 - The general appearances, materials, workmanship, and standard of finish.
 - Dimensional check.
 - Alignment to be demonstrated.

6.6 PACKAGE TEST

- 6.6.1 A full function test of completed package shall be performed. The satisfactory operation of all indicators, selectors and controllers shall be demonstrated.
- 6.6.2 The correct operation of all controllers, alarm and fault protection equipment and indicators shall be demonstrated and if necessary, fault simulations.
- 6.6.3 SELLER shall submit a FAT procedure with a test schedule covering all items within the scope of supply.
- 6.6.4 SELLER shall prepare a FAT procedure for the package and submit for BUYER approval.
- 6.6.5 FAT will be witnessed by BUYER representatives. SELLER shall invite CLASS surveyor for FAT. The advance notice for tests schedule shall be forwarded to BUYER within the deadline stated in EXHIBIT V - DIRECTIVES FOR ACQUISITIONS.
- 6.6.6 Acceptance of the FAT will not be considered as the final acceptance test of the package.

6.7 ASSEMBLY ASSISTANCE AND COMMISSIONING REQUIREMENTS

- 6.7.1 SELLER is responsible for assembly supervision of the equipment, including the assembly of components to be delivery as loose parts (for example, some components of the pumps, like stuffing box; some internals of pressure vessels, etc.).
- 6.7.2 SELLER is responsible for pre-commissioning and commissioning supervision of the equipment/system. SELLER shall submit pre-commissioning and commissioning tests procedures for BUYER approval. Final acceptance shall be on satisfactory completion of commissioning tests as specified by BUYER.

| _ | TECHNICAL SPECIFICATION | No. I-ET-3010.2Q-1251-560-P | 4X-003 REV: A |
|-----------|-------------------------------------|-----------------------------|----------------------|
| BR | MARLIM | LESTE E SUL | SHEET: 23 of 24 |
| PETROBRAS | VACUUM DEAERATION UNIT (UT-1251003) | | ESUP |
| | VACOUM DEAERAT | ION UNIT (UT-1251003) | INTERNAL |

- 6.7.3 An Initial Service Safety Inspection shall be performed on the piping and on the static equipment of the Unit (pressure vessels, heat exchangers, and so on) once the Unit itself has been erected to its final location.
- 6.7.4 Requirements of I-ET-3010.00-1200-200-P4X-115- REQUIREMENTS FOR PIPING FABRICATION AND COMMISSIONING shall be attended.
- 6.7.5 SELLER shall comply with the requirements of I-MD-3010.2Q-1200-970-P4X-001 COMISSIONING DESCRIPTIVE MEMORANDUM.

7 SELLER RESPONSIBILITY

7.1 GENERAL

- 7.1.1 SELLER shall assume sole contractual and total engineering responsibility for the package equipment.
- 7.1.2 SELLER's responsibility shall also include, but is not limited to:
 - Technical responsibility for the entire scope of supply.
 - Resolving all engineering questions and/or problems relating to design and manufacture.
 - All coordination with manufacturers and collection of all details, drawings, calculations, and data to achieve optimum design and full submission of the documents requested in the specification.
 - Providing details as requested of any sub-vendors relating to design and manufacture.
 - To submit to the certifying authority the documentation as described in the latest edition of their rules for equipment on offshore facilities.
 - Installation at site by others, however, presence of supervision will be required.
 - SELLER's responsibility shall also include Commissioning & Training for operation.
 - Pre-Commissioning.
 - Attend HAZOP meetings arranged by BUYER and update the design with its recommendations.
- 7.1.3 Any exclusion and/or alternative to that specified in this Technical Specification, including the use of the SELLER's standard and exclusive technology, shall be presented in a Deviation List, subject to the BUYER's acceptance during the clarification phase, prior to the submission of the proposal. Otherwise, the requirements contained herein will be considered as "Agreed" and therefore required.

8 PREPARATION FOR SHIPMENT

8.1 MARKING

- 8.1.1 All items supplied to this specification shall be marked for identification against a certificate or relevant test documentation. Marking shall be such that it will not damage or impair the component.
- 8.1.2 Items that cannot be identified shall be rejected. Rejected items may be re-certified by carrying out all relevant testing, with prior approval of BUYER.

8.2 SHIPMENT PACKING



- 8.2.1 SELLER shall provide suitable outdoor storage packing, if planning to store this equipment in an outdoor area, taking into consideration access for heating elements control/monitoring.
- 8.2.2 All open ends of tubes on the equipment shall be treated and closed off by plastic caps and taped. Small bore threaded connections as cables entrances, shall be temporary plugged.
- 8.2.3 All carbon steel vessels, stainless steel instruments/piping/tubing, etc. shall be protected with corrosion inhibitor prior to shipment.
- 8.2.4 The package shall be protected from corrosion.
- 8.2.5 Vulnerable instruments shall be removed and packed separately for shipment.
- 8.2.6 Transportation bracing/support shall be used where necessary and shall be clearly identified as temporary.
- 8.2.7 All crates and boxes will contain sufficient moisture absorbing agent to avoid condensation.
- 8.2.8 SELLER shall specify any limitations applicable to the transport and installation phase.